

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2 (-1A, B-1, VB-1)	STEPHENSON	386	33
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
P-92-029-02		SCHED-10 OF 15		
CONTRACT #64799				

60100915 PIPE DRAINS 6" FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20	95+50	RT	113+00	RT	50
TOTAL FOR Y050 FRONTAGE ROAD:					50
TOTAL QUANTITY:					50

60100925 PIPE DRAINS 8" FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20	95+50	RT	113+00	RT	50
TOTAL FOR Y050 FRONTAGE ROAD:					50
TOTAL QUANTITY:					50

60100945 PIPE DRAINS 12" FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20	95+50	RT	113+00	RT	50
TOTAL FOR Y050 FRONTAGE ROAD:					50
TOTAL QUANTITY:					50

60100965 PIPE DRAINS 18" FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20	95+50	RT	113+00	RT	50
TOTAL FOR Y050 FRONTAGE ROAD:					50
TOTAL QUANTITY:					50

60107600 PIPE UNDERDRAINS 4" FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20	576+25	51 RT	590+66	51 RT	1,441
TOTAL FOR 1000-2A ROADWAY:					1,441
FRONTAGE ROAD					
170+75	17 LT	-	170+75	24 RT	41
173+25	17 LT	-	173+25	24 RT	41
175+75	17 LT	-	175+75	24 RT	41
177+75	17 LT	-	177+75	24 RT	41
180+25	17 LT	-	180+25	24 RT	41
TOTAL FOR Y050 FRONTAGE ROAD:					205
TOTAL QUANTITY:					1,646

60220105 MANHOLES, TYPE A, 4'-DIAMETER, WITH MEDIAN INLET (604106) EACH					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20	528+00.00	0.00 CL			1
TOTAL FOR 1000-2A ROADWAY:					1
TOTAL QUANTITY:					1

60242400 INLETS, SPECIAL EACH					
STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
175+85.00	12.00 RT		LT		2
179+60.00	12.00 RT				1
173+35.00	12.00 RT				1
178+25.00	12.00 RT		LT		2
TOTAL FOR Y050 FRONTAGE ROAD:					6
TOTAL QUANTITY:					6

60240361 INLETS, TYPE B, WITH MEDIAN INLET (604101) EACH					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20	572+00.00	0.00 CL			1
552+00.00	0.00 CL				1
598+25.00	0.00 CL				1
601+50.00	0.00 CL				1
TOTAL FOR 1000-2A ROADWAY:					4
TOTAL QUANTITY:					4

60246805 MEDIAN INLET (604106) EACH					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20	152+00.00	0.00 CL			1
TOTAL FOR 1000-2A ROADWAY:					1
TOTAL QUANTITY:					1

60260100 INLETS TO BE ADJUSTED EACH					
STATION	OFFSET	-	STATION	OFFSET	UNIT
IL 26	733+52.0				1
TOTAL FOR 1000-1A IL 26					1
TOTAL QUANTITY:					1

60600095 CLASS SI CONCRETE (OUTLET) CU YD					
STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
170+00	RT		2.41 CY + 30' (0.069)		4.5
179+80	LT		2.41 CY + 30' (0.069)		4.5
TOTAL FOR Y050 FRONTAGE ROAD:					9.0
TOTAL QUANTITY:					9.0

60605000 COMBINATION CONCRETE CURB AND CUTTER, TYPE B-6.24 FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
IL 26	724+06.50	LT	726+47.30	LT	241
	724+06.50	RT	726+47.30	RT	241
TOTAL FOR 1000-1A IL 26:					482
FRONTAGE ROAD					
170+39.73	LT		179+55.84	LT	916
170+39.73	RT		182+24.38	RT	1,185
173+85.00	RT		ENTRANCE		100
176+95.00	RT		ENTRANCE		102
180+00.00	RT		ENTRANCE		55
TOTAL FOR Y050 FRONTAGE ROAD:					2,357
TOTAL QUANTITY:					2,839

60618300 CONCRETE MEDIAN SURFACE, 4 INCH SQ FT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
IL 26	724+06.50	CL	726+47.30	RT	6 2,900
TOTAL FOR 1000-1A IL 26					2,900
TOTAL QUANTITY:					2,900

60620000 CONCRETE MEDIAN, TYPE SB-6.24 SQ FT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
IL 26	726+47.30	RT	729+07.40	RT	11.5 2,940
TOTAL FO					2,940
TOTAL QUANTITY:					2,940

60900515 CONCRETE THRUST BLOCKS EACH					
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20	572+00	LT			1
TOTAL FOR 1000-2A ROADWAY:					1
TOTAL QUANTITY:					1

61100500 EXPLORATION TRENCH 52" DEPTH FOOT					
STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD	95+50	RT	113+00	RT	200
TOTAL FOR Y050 FRONTAGE ROAD:					200
TOTAL QUANTITY:					200

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 301 (US RTE. 20)
FROM BOLTON ROAD TO WEST OF IL RTE. 26
SCHEDULE OF QUANTITIES



SCALE: DATE: 01-22-10
DRAWN BY: AJP
CHECKED BY: RMH