

70300220 TEMPORARY PAVEMENT MARKING - LINE 4" FOOT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD						
Stage IIA	173+49	LT		180+67	LT	718
	174+19	RT		176+00	RT	181
	177+32	RT		180+67	RT	335
Stage IIB	171+67	LT		180+43	LT	876
	172+10	LT		173+67	LT	157
	174+04	LT		176+65	LT	261
	177+12	LT		180+34	LT	322
	172+73	LT		173+67	LT	94
	174+04	LT		176+65	LT	261
	177+12	LT		180+12	LT	300

FRONTAGE ROAD ENT.						
Stage IIA	6+15	RT		7+59	RT	144
	6+46	RT		7+59	RT	113

TOTAL FOR Y050 FRONTAGE ROAD: 3,762

TOTAL QUANTITY: 3762

70300625 TEMPORARY PAVEMENT MARKING - LINE 4" FOOT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
US20						
Stage I	619+43	RT		647+00	LT	2,757
Stage III	576+00	RT/LT		591+00	RT/LT	6,970
	576+00	RT/LT		591+00	RT/LT	6,640

TOTAL FOR 1000-2A ROADWAY: 16,367

FRONTAGE ROAD						
Stage IIB	171+36	LT		171+67	LT	31
	171+20	-		172+15	LT	95
	171+26	RT		172+88	LT	162
	180+40	LT		180+65	LT	25

FRONTAGE ROAD ENTRANCE						
Stage IIB	6+72	LT		7+56	LT	84
	6+45	LT		7+62	LT	117
	6+34	LT		7+62	LT	128

HEINE ROAD						
Stage IIB	18+33	LT		22+69	LT	436
	18+33	-		22+36	-	403
	18+33	RT		22+66	RT	433

TOTAL FOR Y050 FRONTAGE ROAD: 1,914

IL 26						
Stage IA	725+76	LT		729+20	LT	344
	729+96	LT		731+06	LT	110
	725+76	LT		729+20	LT	344
	729+96	LT		731+06	LT	110
	725+76	RT		729+20	RT	344
	725+76	RT		729+20	RT	344

Stage IIA	726+43	RT		729+34	RT	291
	726+43	RT		729+34	RT	291

Stage IIB	727+15	RT		728+53	RT	138
	729+26	RT		730+78	RT	152
	727+15	RT		728+53	RT	138
	729+26	RT		730+78	RT	152

Stage III	699+69	-		709+27	LT	958
	710+13	LT		712+71	LT	258
	710+13	LT		712+71	LT	258
	712+57	-		717+94	LT	537
	715+50	-		717+94	LT	244
	719+00	LT		729+17	LT	1,017
	730+01	LT		741+51	LT	1,150
	699+69	-		709+27	RT	958
	710+13	RT		712+57	-	244
	710+13	RT		715+50	-	537
	715+36	RT		717+94	RT	258
	715+36	RT		717+94	RT	258
	719+00	RT		729+17	RT	1,017
	730+01	RT		735+00	RT	499

TOTAL FOR 1000-1A IL 26 10,951

TOTAL QUANTITY: 29,232

70300660 TEMPORARY PAINT PAVEMENT MARKING - LINE 24" FOOT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD ENT.						
Stage IIB	7+62	LT				11

TOTAL FOR Y050 FRONTAGE ROAD: 11

TOTAL QUANTITY: 11

70301000 WORK ZONE PAVEMENT MARKING REMOVAL SQ FT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
US20 - PHASE 1						5,456

TOTAL FOR 1000-2A ROADWAY: 5,456

IL 26 - PHASE 1						3,650
-----------------	--	--	--	--	--	-------

TOTAL FOR 1000-1A IL 26 3,650

TOTAL QUANTITY: 9,106

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS SQ FT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
IL 26 - NORTHBOUND						47
IL 26 - SOUTHBOUND						47

TOTAL FOR 1000-1A IL 26 94

TOTAL QUANTITY: 94

78000280 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT

	STATION	OFFSET	-	STATION	OFFSET	UNIT
US20						
	576+00	25.00 RT		591+00	WHT EDGE	1,500
	576+00	51.00 RT		591+00	WHT EDGE	1,500
	576+00	39.00 RT		591+00	YEL CL	375

TOTAL FOR 1000-2A ROADWAY: 3,375

IL 26						
	730+03	4.00 RT		734+87	YEL MEDIAN	1,983
	723+00	23.00 RT		729+13	WHT SK DSH	230
	724+00	23.00 LT		738+91	WHT SK DSH	350
	730+00	23.00 LT		739+00	WHT SK DSH	18,469
	730+00	10.60 RT		734+85	WHT DOUBLE	970
	730+00	4.60 RT		734+85	WHT DOUBLE	970

TOTAL FOR 1000-1A IL 26 22,972

TOTAL QUANTITY: 26,347

TRAFFIC CONTROL AND PROTECTION-LUMP SUM										
	PAY ITEM *									
	70100460	70100500	70100200		70100800	70100320	70102632	70102635		
TRAFFIC CONTROL AND PROTECTION STANDARD *										
	701306	701326	701331	701400	701401	701422	701602	701701	40.1**	94.2**
CONSTRUCTION STAGE										
US 20										
STAGE I		X		X	X					
STAGE III										
FRONTAGE ROAD										
STAGE I		X							X	
STAGE IIA	X	X						X	X	
STAGE IIB	X		X					X		
STAGE IIC		X						X		
STAGE III										
HEINE ROAD										
STAGE I										
STAGE IIA										
STAGE IIB									X	
BIKE PATH/KLEVER ROAD										
STAGE IA	X	X								
STAGE I										
IL 26										
STAGE I								X		
STAGE IIA		X						X	X	
STAGE IIB			X					X		
STAGE IIC		X						X		
STAGE III					X	X				X

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 301 (US RTE. 20)  
FROM BOLTON ROAD TO WEST OF IL RTE. 26

SCHEDULE OF QUANTITIES

SCALE:  
DATE: 01-22-10

DRAWN BY: AJP  
CHECKED BY: RMH

