

BITUMINOUS SCHEDULE

STATIONS	REMARKS	LENGTH FT.	PROPOSED SURFACE AREAS			40600200	40600300	40603080	40603085	40603310	40603310	40603335	40603340	48100100	48203021	
			PAVEMENT		SHOULDER		BIT. PRIME	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0,N50	HOT-MIX ASPHALT BINDER COURSE, IL-19.0,N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C",N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "C",N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D",N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D",N70	AGGREGATE SHOULDERS, TYPE A	HOT-MIX ASPHALT SHOULDERS, 6"
			OVERALL AREA SQ. YD.	BIT. AREA SQ. YD.	AGG. AREA SQ. YD.	2 APPLICATIONS TON	TON	TON - 4"	TON - 10 1/2"	TON - 2"	TON - 3"	TON - 2"	TON - 2"	TON	SQ. YD.	
US 20 576+25 - 590+66	TURNING LANES	1,441		2,562	801	7.33	7.69			286.92			358.65	2,561.8		
FRONTAGE ROAD 95+50 - 182+00	MAINLINE	17,245	24,488		9,986	69.44	36.42	5,461.95				2,743.06	3,355.40			
95+50 - 182+00	BIKE PATH	17,245	8,792			12.57				1,477.02						
172+00 - 180+00	TEMP. PAV.	800	3,365			9.62	5.05	282.63			376.84					
HEINE ROAD 8+00 - 22+77	MAINLINE	1,477	4,022		1,970	11.50	6.03	900.86			450.43		661.85			
8+00 - 22+77	BIKE PATH	1,477	1,599			2.29				268.61						
FRONTAGE ROAD ENTRANCE 6+00 - 7+68		168	1,755		575	5.02	2.63	393.20			196.60		193.32			
IL 26 724+30 - 734+87	MAINLINE	1,057	2,562			7.84	2.74	1,075.01				204.76				
725+76 - 729+20	TEMP. PAV.										357.73					
KLEVER ROAD 5580+06 - 5583+67	CUL DE SAC	361	1,505			4.61	2.42	337.08			168.54					
GRAND TOTAL			48,087	2,562	13,332	130	63	7,376	1,075	287	1,746	2,033	4,303	205	4,569	2,562

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 301 (US RTE. 20)
FROM BOLTON ROAD TO WEST OF IL RTE. 26

SCHEDULE OF QUANTITIES

SCALE: _____ DRAWN BY MGH
DATE: 01-22-10 CHECKED BY SJV

