

SUMMARY OF QUANTITIES				100% STATE
CODE NO.	ITEM	UNIT	TOTAL	CONSTR. CODE I000 FAP 673 (IL 116)
20400800	FURNISHED EXCAVATION	CU YD	220	220
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	34433	34433
40600300	AGGREGATE (PRIME COAT)	TON	1056	1056
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	78	78
40600525	LEVELING BINDER (HAND METHOD), N50	TON	130	130
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	10916	10916
40600990	TEMPORARY RAMP	SQ YD	643	643
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	21829	21829
40800050	INCIDENTAL HOT MIX ASPHALT SURFACING	TON	913	913
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	259850	259850
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8129	8129
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4901	4901
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	21	21
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	22957	22957
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	141	141
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	149271	149271
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	17132	17132
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	430	430
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	338	338
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2552	2552
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	141	141
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10660	10660
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	138	138
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	430	430
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	338	338
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	271880	271880
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	33988	33988
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	976	976
* 78200300	PRISMATIC CURB REFLECTOR	EACH	91	91
78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	835	835
X0322729	MATERIAL TRANSFER DEVICE	TON	21,829	21,829

\* SPECIALTY ITEM

FILE NAME =	USER NAME = corcoranlm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pw\work\pwidat\corcoranlm\dms64429\066845-SHEETS.dgn	DRAWN -	REVISED -	673			(111,112)RS-2&(112)RS-5	LIVINGSTON	12	3	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66845							
PLOT DATE = Feb 03, 2010 - 11:01:50 AM	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	(ILLINOIS) FED. AID PROJECT	