

RESURFACING SCHEDULE														
LOCATION	LENGTH	PVMT AREA	HMA SURF CSE	LEVEL BINDER (MM)	HMA SURF REM 3/4"	HMA SURF REM 2-1/4"	HMA SURF REM BUTT JT	TEMP RAMP	BIT MAT (PR CT)	AGG (PR CT)	MIX FOR CRACKS, JOINTS & FLGWYS	LEVEL BINDER (HM)	HMA SHLDR	AGG SHLD WEDGE TY B
STA TO STA	FOOT	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	TON
424+50 TO 516+40	9190	30633.3	2573	1287	30533.0		100	6.7	3982	122.5	9.19	15.32		523.3
516+40 TO 517+00 MILLING TAPER	60	2144.1	180	90		2144		6.7	279	8.6	0.64	1.07		3.4
517+00 TO 526+00 *	900	4944.1	415	208		4944		20	643	19.8	1.48	2.47		
526+00 TO 526+60 MILLING TAPER	60	2144.1	180	90		2144		6.7	279	8.6	0.64	1.07		3.4
526+60 TO 660+53	13393	44643.3	3750	1875	44543.0		100	6.7	5804	178.6	13.39	22.32		762.7
SN 050-0159-OMISSION 660+53 TO 662+47	194													
662+47 TO 710+53	4806	16020.0	1346	673	15920.0		100	6.7	2083	64.1	4.81	8.01		273.7
710+53 TO 894+80	18427	49138.7	4128	2064	49039.0		100	6.7	6388	196.6	14.74	24.57	2580	699.5
TOTAL			12572	6287	140035	9232	400	60.2	19458	598.8	44.89	74.8	2580	2266.0

* US 52(E) SHALL BE MILLED AND RESURFACED FROM STATION 0+00 TO STATION 3+50

PAVEMENT MARKING SCHEDULE														
LOCATION	LENGTH	PAINT PAVEMENT MARKING 4"		PAINT PVMT MARK 6"	PAINT PVMT MARK 8"	PAINT PVMT MARK 12"	PAINT PVMT MARK 24"	PAINT PVMT MARK LETTERS & SYMB	RAISED REFLECT PVMT MARK	RAISED REFLECT PVMT MARK REM	PRISMATIC CURB REFLECT	SHORT TERM PVMT MARK	WORK ZONE PVMT MARK REM	
		WHITE	YELLOW	YELLOW	WHITE	WHITE	WHITE	SQ FT	EACH	EACH	EACH	FOOT	SQ FT	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT							
IL 23:														
424+50 TO 660+53	23603	94412	6082	11802					295	295		7081	786	
SN 050-0159-OMISSION 660+53 TO 662+47	194	776		97								58	6	
662+47 TO 710+53	4806	19224	4828	2403					60	60		1442	160	
710+53 TO 894+80	18427	73708		9214					230	230		5528	614	
US 52 (E):									0	0				
0+12 TO 3+50	338	1352		169	920	480	68	62.4	21	21	16	101	11	
SUBTOTAL		189472	10910	23685	920	480	68	62.4	606	606	16	14210	1577	
PROJECT TOTAL		200382		23685	920	480	68	62.4	606	606	16	14210	1577	

THE PERMANENT PAVEMENT MARKING SHALL BE APPLIED TWICE TO INCREASE THE THICKNESS. ADDITIONAL QUANTITY HAS BEEN INCLUDED.

SEEDING SCHEDULE								
SIDEROAD OR DESCRIPTION	STATION	SIDE	SEEDING	FURN	EROSION	NIT	PHOS	POT
			CL 2	EXC	CONTROL	FERT	FERT	FERT
			ACRE	CU YD	BLANKET	NUT	NUT	NUT
					SQ YD	LB	LB	LB
E 1750TH RD	441+16	LT	0.01	1.5	52	0.9	0.9	0.9
E 18TH RD	476+80	RT	0.01	1.5	52	0.9	0.9	0.9
US 52E	523+12.88	RT	0.01	1.5	52	0.9	0.9	0.9
38TH RD	524+61	LT	0.01	1.5	52	0.9	0.9	0.9
PE/MBTO	546+65	RT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	559+17	RT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	560+40	RT	0.01	1.5	56	0.9	0.9	0.9
MBTO	584+50	RT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	585+71	LT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	586+78	LT	0.01	1.5	56	0.9	0.9	0.9
N 40TH RD	628+97	RT	0.01	1.5	52	0.9	0.9	0.9
N 40TH RD	631+62	LT	0.01	1.5	52	0.9	0.9	0.9
N 4050TH RD	658+29	LT	0.01	1.5	52	0.9	0.9	0.9
PE/MBTO	663+70	LT	0.01	1.5	52	0.9	0.9	0.9
MBTO	663+70	RT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	674+00	LT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	674+50	LT	0.01	1.5	56	0.9	0.9	0.9
N 41ST RD	682+27	RT	0.01	1.5	52	0.9	0.9	0.9
MBTO	686+40	RT	0.01	1.5	56	0.9	0.9	0.9
PE/MBTO	704+14	RT	0.01	1.5	56	0.9	0.9	0.9
N 4101ST RD	710+53	LT	0.01	1.5	52	0.9	0.9	0.9
N 42ND RD	737+82	LT	0.01	1.5	52	0.9	0.9	0.9
N 42ND RD	737+82	RT	0.01	1.5	52	0.9	0.9	0.9
N 4253RD RD	788+34	LT	0.01	1.5	52	0.9	0.9	0.9
N 4253RD RD	788+34	RT	0.01	1.5	52	0.9	0.9	0.9
N 44TH RD	843+73	LT	0.01	1.5	52	0.9	0.9	0.9
N 44TH RD	843+73	RT	0.01	1.5	52	0.9	0.9	0.9
TOTAL			0.27	40.5	1448	24.3	24.3	24.3

TEMPORARY PAVEMENT MARKING SCHEDULE									
LOCATION	LENGTH	TEMPORARY PAVEMENT MARKING 4"		TEMP PVMT MARK 6"	TEMP PVMT MARK 8"	TEMP PVMT MARK 12"	TEMP PVMT MARK 24"	TEMP PVMT MARK LETTERS & SYMB	
		WHITE	YELLOW	YELLOW	WHITE	WHITE	WHITE	SQ FT	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
IL 23:									
424+50 TO 660+53	23603	47206	3041	5901					
SN 050-0159-OMISSION 660+53 TO 662+47	194	388		49					
662+47 TO 710+53	4806	9612	2414	1202					
710+53 TO 894+80	18427	36854		4607					
US 52 (E):									
0+12 TO 3+50	338	676		169	460	240	34	31.2	
SUBTOTAL		94736	5455	11928	460	240	34	31.2	
PROJECT TOTAL		100191		11928	460	240	34	31.2	