

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		1000-2A
		UNIT	TOTAL QUANTITY	100% STATE ROADWAY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	422	422
20400800	FURNISHED EXCAVATION	CU YD	15	15
25100630	EROSION CONTROL BLANKET	SQ YD	227	227
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9463	9463
40600300	AGGREGATE (PRIME COAT)	TON	146	146
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17
40600525	LEVELING BINDER (HAND METHOD), N50	TON	29	29
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	2998	2998
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	221	221
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5997	5997
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	270	270
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	59384	59384
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	14064	14064
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9015	9015
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	244.8	244.8
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9524	9524
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	10520	10520
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	144	144
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	992	992
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4	122.4
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	72	72
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	47614	47614
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	5260	5260
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	268	268
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	214	214
X0322729	MATERIAL TRANSFER DEVICE	TON	5997	5997
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEMS

Rev.

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\PWIDOT\DUNCANBD\0129029\1386951-shit-cover.dgn	DRAWN -	REVISED -	324			(25)RS-4	DEKALB	17	3	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 66951				
PLOT DATE = Jan 19, 2010 - 10:45:48 AM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							