

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	39

* (58,74-66)&(74-67&68)RS-1

SCHEDULES

48203100 HOT MIX ASPHALT SHOULDERS (CONT'D)

		STATION	TO	STATION		LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	SHOULDER THICKNESS (INCHES)	48203100 HMA SHLD (TON)	40800100 BIT MATLS PR CT (GAL)	40600300 AGG PR CT (TONS)
I-72 INTERCHANGE NO. 169 AT FAS 1532 (OLD 47) RAMP SHOULDERS												
RAMP A	RT	101+54.29		RT 101+99.29		45.00	8.0	43.1	1.50	3.6	4.3	0.1
RAMP A	RT	101+99.29		RT 110+77.00		877.71	8.0	780.2	2.50	109.2	78.0	1.6
RAMP A	RT	110+77.00		RT 117+44.40		667.40	8.0	593.2	3.75	124.6	59.3	1.2
RAMP A	RT	117+44.40		RT 119+94.40	TAPER	250.00	VAR	250.0	3.75	52.5	25.0	0.5
RAMP A	LT	101+54.29		LT 101+99.29		45.00	4.0	20.0	1.50	1.7	2.0	0.0
RAMP A	LT	101+99.29		LT 110+77.00		877.71	4.0	390.1	2.50	54.6	39.0	0.8
RAMP A	LT	110+77.00		LT 114+59.00	GORE	382.00	VAR	307.4	3.75	64.6	30.7	0.6
RAMP B	RT	200+00.00		RT 202+67.00		267.00	10.0	296.7	3.75	62.3	29.7	0.6
RAMP B	RT	202+67.00		RT 206+50.00	NO TAPER	383.00	8.0	340.4	3.75	71.5	34.0	0.7
RAMP B	RT	206+50.00		RT 215+30.50		880.50	8.0	782.7	2.50	109.6	78.3	1.6
RAMP B	RT	215+30.50		RT 215+75.50		34.79	8.0	30.9	1.50	2.6	3.1	0.1
RAMP B	LT	205+82.00		LT 206+50.00	GORE	80.41	VAR	115.2	3.75	24.2	11.5	0.2
RAMP B	LT	206+50.00		LT 215+30.50		880.50	4.0	391.3	2.50	54.8	39.1	0.8
RAMP B	LT	215+30.50		LT 215+75.50		40.35	4.0	17.9	1.50	1.5	1.8	0.0
RAMP C	RT	301+15.00		RT 301+80.00		45.00	8.0	40.0	1.50	3.4	4.0	0.1
RAMP C	RT	301+80.00		RT 310+18.00		858.00	8.0	762.7	2.50	106.8	76.3	1.5
RAMP C	RT	310+18.00		RT 319+24.00		906.00	8.0	805.3	3.75	169.1	80.5	1.6
RAMP C	LT	301+15.00		LT 301+80.00		45.00	4.0	20.0	1.50	1.7	2.0	0.0
RAMP C	LT	301+80.00		LT 310+18.00		858.00	4.0	381.3	2.50	53.4	38.1	0.8
RAMP C	LT	310+18.00		LT 311+23.00	GORE	105.00	VAR	151.7	3.75	31.9	15.2	0.3
RAMP D	RT	400+00.00		RT 402+50.00	TAPER	250.00	VAR	250.0	3.75	52.5	25.0	0.5
RAMP D	RT	402+50.00		RT 406+52.00		402.00	8.0	357.3	3.75	75.0	35.7	0.7
RAMP D	RT	406+52.00		RT 418+07.00		1155.00	8.0	1026.7	2.50	143.7	102.7	2.1
RAMP D	RT	418+07.00		RT 418+52.00		118.50	8.0	105.3	1.50	8.8	10.5	0.2
RAMP D	LT	404+67.00		LT 406+52.00	GORE	185.00	VAR	214.9	3.75	45.1	21.5	0.4
RAMP D	LT	406+52.00		LT 418+07.00		1155.00	4.5	577.5	2.50	80.9	57.8	1.2
RAMP D	LT	418+07.00		LT 418+52.00		45.00	4.5	22.5	1.50	1.9	2.3	0.0
SUB-TOTAL =										1511.4	907.4	18.1
TOTAL =										41780.0	29962.2	599.2
USE =										41780.0	29965.0	600.0

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\pwwork\pwwork\cear1lock\jd\0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear1lockjd

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 6 of 6 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.