

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	43

\*(58,74-66)&(74-67&68)RS-1

## SCHEDULES

**48203029 HOT MIX ASPHALT SHOULDERS, 8 INCH**

		STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	HMA SHLD 8 THICKNESS (INCHES)	HMA SHLD 8 (TON)	48203029 AREA (SQ YD)
<b>I-72 INTERCHANGE NO. 169 AT FAS 1532 ( OLD 47 ) RAMP SHOULDERS</b>									
RAMP A	RT	101+54.29	RT	101+99.29	45.00	2.0	8.00	4.5	10.0
RAMP A	RT	101+99.29	RT	110+77.00	877.71	2.0	8.00	87.4	195.0
RAMP A	RT	110+77.00	RT	117+44.40	667.40	2.0	8.00	66.4	148.3
RAMP A	RT	117+44.40	RT	119+94.40	250.00	2.0	8.00	24.9	55.6
RAMP B	RT	200+00.00	RT	202+67.00	267.00	2.0	8.00	26.6	59.3
RAMP B	RT	202+67.00	RT	206+50.00	383.00	2.0	8.00	38.1	85.1
RAMP B	RT	206+50.00	RT	215+30.50	880.50	2.0	8.00	87.7	195.7
RAMP B	RT	215+30.50	RT	215+75.50	34.79	2.0	8.00	3.5	7.7
RAMP C	RT	301+15.00	RT	301+60.00	45.00	2.0	8.00	4.5	10.0
RAMP C	RT	301+60.00	RT	310+18.00	858.00	2.0	8.00	85.4	190.7
RAMP C	RT	310+18.00	RT	319+24.00	906.00	2.0	8.00	90.2	201.3
RAMP D	RT	400+00.00	RT	402+50.00	250.00	2.0	8.00	24.9	55.6
RAMP D	RT	402+50.00	RT	406+52.00	402.00	2.0	8.00	40.0	89.3
RAMP D	RT	406+52.00	RT	418+07.00	1155.00	2.0	8.00	115.0	256.7
RAMP D	RT	418+07.00	RT	418+52.00	118.50	2.0	8.00	11.8	26.3
<b>SUB-TOTAL =</b>								<b>710.8</b>	<b>1586.6</b>
<b>TOTAL =</b>								<b>3539.5</b>	<b>7900.6</b>
<b>USE =</b>								<b>3540.0</b>	<b>7900.0</b>

PLOT DATE = 2/8/2010  
 FILE NAME = c:\pwwork\pwwork\cear\lock\j\d0109678\TEXT2899.DGN  
 PLOT SCALE = 105.8824 / IN.  
 USER NAME = cear\lockj

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72  
SECTION (58,74-66)&(74-67&68)RS-1  
PIATT COUNTY  
Sheet 4 of 4 Sheets

SCALE: NONE      DRAWN BY: CADD  
DATE: 12/15/09      CHECKED BY: R.T.B.