

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	44

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

48102100 AGGREGATE WEDGE SHOULDER TYPE B

		STATION	IQ	STATION		LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	SHOULDER THICKNESS (INCHES)	(TON)
I-72 MEDIAN SHOULDERS										
	I-72 EB	LT		LT	932+59.22	2259.2	2.0	502.0	2.25	61.2
	I-72 EB	LT		LT	965+00.00	3240.8	2.0	720.2	2.25	87.8
	I-72 EB	LT		LT	1210+00.00	24500.0	2.0	5444.4	2.25	663.5
	I-72 EB	LT		LT	1278+85.96	6886.0	2.0	1530.2	2.25	186.5
	I-72 EB	LT		LT	1279+32.96	47.0	2.0	10.4	2.25	1.3
	I-72 EB	LT		LT	1280+39.13	47.0	2.0	10.4	2.25	1.3
	I-72 EB	LT		LT	1280+86.13	2805.9	2.0	623.5	2.25	76.0
	I-72 EB	LT		LT	1308+92.00	11239.0	2.0	2497.6	2.25	304.4
	I-72 EB	LT		LT	1421+31.00	55.5	2.0	12.3	2.25	1.5
	I-72 EB	LT		LT	1428+63.44	55.5	2.0	12.3	2.25	1.5
	I-72 EB	LT		LT	1429+18.90	718.1	2.0	159.6	2.25	19.4
	I-72 EB	LT		LT	1436+37.00	58.2	2.0	12.9	2.25	1.6
	I-72 EB	LT		LT	1439+18.28	57.7	2.0	12.8	2.25	1.6
	I-72 EB	LT		LT	1439+76.00	2444.0	2.0	543.1	2.25	66.2
	I-72 EB	LT		LT	1464+20.00	2842.0	4.0	1263.1	2.25	153.9
	I-72 EB	LT		LT	1492+62.04	679.0	4.0	301.8	4.25	69.5
	I-72 EB	LT		LT	1499+41.06	5347.6	4.0	2376.7	4.25	547.1
	I-72 EB	LT		LT	1162+63.35	4960.1	4.0	2204.5	4.25	507.5
	I-72 EB	LT		LT	1216+11.00	3439.6	4.0	1528.7	4.25	351.9
	I-72 EB	LT		LT	1265+30.54	84.0	4.0	37.3	2.25	4.6
	I-72 EB	LT		LT	1299+70.10	54.0	4.0	24.0	2.25	2.9
	I-72 EB	LT		LT	1302+62.80	7472.2	4.0	3321.0	4.25	764.5
	I-72 EB	LT		LT	1303+16.80					
	I-72 EB	LT		LT	1377+89.00					
	SUB-TOTAL =									3875.7

I-72 MEDIAN SHOULDERS (CONTINUED)

	I-72 WB	RT		RT	932+59.22	2259.2	2.0	502.0	2.25	61.2
	I-72 WB	RT		RT	965+00.00	3240.8	2.0	720.2	2.25	87.8
	I-72 WB	RT		RT	1210+00.00	24500.0	2.0	5444.4	2.25	663.5
	I-72 WB	RT		RT	1279+13.88	6913.9	2.0	1536.4	2.25	187.3
	I-72 WB	RT		RT	1279+60.88	47.0	2.0	10.4	2.25	1.3
	I-72 WB	RT		RT	1280+67.05	47.0	2.0	10.4	2.25	1.3
	I-72 WB	RT		RT	1281+14.05	2778.0	2.0	617.3	2.25	75.2
	I-72 WB	RT		RT	1308+92.00	11333.0	2.0	2518.4	2.25	306.9
	I-72 WB	RT		RT	1422+25.00	55.5	2.0	12.3	2.25	1.5
	I-72 WB	RT		RT	1422+80.50	55.5	2.0	12.3	2.25	1.5
	I-72 WB	RT		RT	1429+57.42	752.1	2.0	167.1	2.25	20.4
	I-72 WB	RT		RT	1430+12.90	57.9	2.0	12.9	2.25	1.6
	I-72 WB	RT		RT	1437+65.00	57.9	2.0	12.9	2.25	1.6
	I-72 WB	RT		RT	1437+65.00	58.0	2.0	12.9	2.25	1.6
	I-72 WB	RT		RT	1440+46.02	2316.0	2.0	514.7	2.25	62.7
	I-72 WB	RT		RT	1441+04.00	2482.1	4.0	1103.2	2.25	134.4
	I-72 WB	RT		RT	1464+20.00	1039.0	4.0	461.8	4.25	106.3
	I-72 WB	RT		RT	1489+02.09	5347.6	4.0	2376.7	4.25	547.1
	I-72 WB	RT		RT	1489+41.06	4960.1	4.0	2204.5	4.25	507.5
	I-72 WB	RT		RT	1162+63.35	3438.1	4.0	1527.1	4.25	351.6
	I-72 WB	RT		RT	1216+11.00	79.0	4.0	35.1	2.25	4.3
	I-72 WB	RT		RT	1265+30.54	66.0	4.0	29.3	2.25	3.6
	I-72 WB	RT		RT	1299+66.62	79.0	4.0	35.1	2.25	4.3
	I-72 WB	RT		RT	1300+45.62	86.0	4.0	29.3	2.25	3.6
	I-72 WB	RT		RT	1302+54.29	7468.7	4.0	3319.4	4.25	764.2
	I-72 WB	RT		RT	1303+20.29					
	I-72 WB	RT		RT	1377+89.00					
	SUB-TOTAL =									3892.7

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\pwwork\pwwork\cear-lock\jd\0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear-lock\jd

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 1 of 5 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.