

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	100

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

PARTIAL DEPTH PATCHING

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PARTIAL DEPTH REMOVAL (sq. yd.)	Z0004800	
						BITUMINOUS MIX FOR PATCHING (ton)	
1273+53.00	EB	DL	6	6	4.0	0.7	
1273+40.00	EB	DL	6	12	8.0	1.3	
1271+23.00	EB	DL	12	12	16.0	2.7	
1270+51.00	EB	DL	15	6	10.0	1.7	
1268+31.00	EB	DL	10	12	13.3	2.2	
1267+64.00	EB	DL	8	6	5.3	0.9	
1265+74.00	EB	DL	6	6	4.0	0.7	
1265+25.00	EB	DL	6	6	4.0	0.7	
1264+13.00	EB	DL	10	12	13.3	2.2	
1262+16.00	EB	DL	6	6	4.0	0.7	
1261+59.00	EB	DL	20	6	13.3	2.2	
1261+32.00	EB	DL	15	6	10.0	1.7	
1258+67.00	EB	DL	6	12	8.0	1.3	
1258+35.00	EB	DL	15	6	10.0	1.7	
1258+08.00	EB	DL	15	6	10.0	1.7	
1250+55.00	EB	DL	6	6	4.0	0.7	
1249+36.00	EB	DL	10	12	13.3	2.2	
1249+11.00	EB	DL	6	6	4.0	0.7	
1246+10.00	EB	DL	12	6	8.0	1.3	
1243+83.00	EB	DL	8	6	5.3	0.9	
1240+25.00	EB	DL	6	6	4.0	0.7	
1237+94.00	EB	DL	6	6	4.0	0.7	
1236+84.00	EB	DL	25	6	16.7	2.8	
1233+10.00	EB	DL	6	6	4.0	0.7	
1232+41.00	EB	DL	6	6	4.0	0.7	
1231+95.00	EB	DL	6	6	4.0	0.7	
1231+85.00	EB	DL	6	6	4.0	0.7	
1231+79.00	EB	DL	6	6	4.0	0.7	
1231+14.00	EB	DL	30	12	40.0	6.7	
1227+45.00	EB	DL	6	6	4.0	0.7	
1224+57.00	EB	DL	6	6	4.0	0.7	
1221+27.00	EB	DL	10	6	6.7	1.1	
1221+02.00	EB	DL	6	6	4.0	0.7	
1220+47.00	EB	DL	6	6	4.0	0.7	
1220+20.00	EB	DL	6	6	4.0	0.7	
1214+97.00	EB	DL	6	12	8.0	1.3	
1210+97.00	EB	DL	6	6	4.0	0.7	
SUB-TOTAL =						291.3	48.9

PARTIAL DEPTH PATCHING (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PARTIAL DEPTH REMOVAL (sq. yd.)	Z0004800	
						BITUMINOUS MIX FOR PATCHING (ton)	
1303+44.00	EB	DL	6	6	4.0	0.7	
1302+04.00	EB	DL	6	6	4.0	0.7	
1301+92.00	EB	DL	6	6	4.0	0.7	
1301+69.00	EB	DL	6	6	4.0	0.7	
1301+51.00	EB	DL	6	6	4.0	0.7	
1301+10.00	EB	DL	6	6	4.0	0.7	
1299+81.00	EB	DL	8	12	10.7	1.8	
1299+57.00	EB	DL	12	6	8.0	1.3	
1299+47.00	EB	DL	6	6	4.0	0.7	
1298+19.00	EB	DL	6	6	4.0	0.7	
1297+16.00	EB	DL	6	6	4.0	0.7	
1295+97.00	EB	DL	6	6	4.0	0.7	
1295+68.00	EB	DL	12	12	16.0	2.7	
1295+10.00	EB	DL	6	6	4.0	0.7	
1294+60.00	EB	DL	6	6	4.0	0.7	
1294+40.00	EB	DL	10	6	6.7	1.1	
1294+10.00	EB	DL	6	6	4.0	0.7	
1293+78.00	EB	DL	6	6	4.0	0.7	
1293+13.00	EB	DL	6	12	8.0	1.3	
1292+99.00	EB	DL	6	12	8.0	1.3	
1292+48.00	EB	DL	6	6	4.0	0.7	
1292+02.00	EB	DL	6	12	8.0	1.3	
1291+59.00	EB	DL	6	6	4.0	0.7	
1290+30.00	EB	DL	6	6	4.0	0.7	
1290+19.00	EB	DL	6	12	8.0	1.3	
1289+80.00	EB	DL	6	6	4.0	0.7	
1289+04.00	EB	DL	10	12	13.3	2.2	
1288+87.00	EB	DL	6	6	4.0	0.7	
1288+40.00	EB	DL	6	6	4.0	0.7	
1286+65.00	EB	DL	6	12	8.0	1.3	
1286+42.00	EB	DL	6	6	4.0	0.7	
1282+05.00	EB	DL	6	6	4.0	0.7	
1279+21.00	EB	DL	6	6	4.0	0.7	
1278+55.00	EB	DL	6	6	4.0	0.7	
1275+05.00	EB	DL	6	6	4.0	0.7	
1274+63.00	EB	DL	6	6	4.0	0.7	
1274+01.00	EB	DL	12	12	16.0	2.7	
1273+74.00	EB	DL	30	6	20.0	3.4	
SUB-TOTAL =						234.7	39.4

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\j\d01019678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cealrlockjd

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 1 of 4 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.