

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	102

* (58,74-66)&(74-67&68)RS-1

SCHEDULES

PARTIAL DEPTH PATCHING (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PARTIAL DEPTH REMOVAL (sq. yd.)	Z0004800	
						BITUMINOUS MIX FOR PATCHING (ton)	
1462+00.00	EB	DL	10	6	6.7	1.1	
1460+54.00	EB	DL	6	6	4.0	0.7	
1454+19.00	EB	DL	6	6	4.0	0.7	
1453+16.00	EB	DL	6	6	4.0	0.7	
1419+46.00	EB	DL	6	6	4.0	0.7	
1416+07.00	EB	DL	6	6	4.0	0.7	
1395+82.00	EB	DL	6	6	4.0	0.7	
1392+33.00	EB	DL	6	6	4.0	0.7	
1390+33.00	EB	DL	10	6	6.7	1.1	
1390+15.00	EB	DL	12	12	16.0	2.7	
1389+15.00	EB	DL	6	6	4.0	0.7	
1388+72.00	EB	DL	8	12	10.7	1.8	
1387+33.00	EB	DL	6	6	4.0	0.7	
1386+54.00	EB	DL	10	6	6.7	1.1	
1385+77.00	EB	DL	10	12	13.3	2.2	
1385+21.00	EB	DL	6	6	4.0	0.7	
1384+20.00	EB	DL	15	12	20.0	3.4	
1387+21.00	EB	DL	6	12	8.0	1.3	
1387+02.00	EB	DL	6	6	4.0	0.7	
1386+42.00	EB	DL	6	6	4.0	0.7	
1386+06.00	EB	DL	6	6	4.0	0.7	
1385+38.00	EB	DL	6	6	4.0	0.7	
1385+03.00	EB	DL	20	6	13.3	2.2	
1383+69.00	EB	DL	6	6	4.0	0.7	
1382+82.00	EB	DL	15	12	20.0	3.4	
1381+76.00	EB	DL	6	6	4.0	0.7	
1378+88.00	EB	DL	12	12	16.0	2.7	
SUB-TOTAL =						201.3	33.8
EAST BOUND TOTAL =						1297.3	218.0

PARTIAL DEPTH PATCHING (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PARTIAL DEPTH REMOVAL (sq. yd.)	Z0004800	
						BITUMINOUS MIX FOR PATCHING (ton)	
1419+58.00	WB	DL	6	6	4.0	0.7	
1419+30.00	WB	DL	6	6	4.0	0.7	
1416+99.00	WB	DL	6	6	4.0	0.7	
1416+31.00	WB	DL	6	6	4.0	0.7	
1413+68.00	WB	DL	6	6	4.0	0.7	
1412+23.00	WB	DL	10	6	6.7	1.1	
1405+91.00	WB	DL	6	6	4.0	0.7	
1404+69.00	WB	DL	30	6	20.0	3.4	
1401+53.00	WB	DL	25	6	16.7	2.8	
1400+61.00	WB	DL	25	6	16.7	2.8	
1398+67.00	WB	DL	6	6	4.0	0.7	
1396+88.00	WB	DL	8	6	5.3	0.9	
1395+24.00	WB	DL	12	6	8.0	1.3	
1394+94.00	WB	DL	6	6	4.0	0.7	
1394+51.00	WB	DL	15	6	10.0	1.7	
1388+25.00	WB	DL	6	6	4.0	0.7	
1386+98.00	WB	DL	10	6	6.7	1.1	
1383+36.00	WB	DL	20	6	13.3	2.2	
1382+51.00	WB	DL	6	6	4.0	0.7	
1377+30.00	WB	DL	6	6	4.0	0.7	
1361+47.00	WB	DL	6	6	4.0	0.7	
1359+56.00	WB	DL	6	6	4.0	0.7	
1346+00.00	WB	DL	6	6	4.0	0.7	
1345+75.00	WB	DL	6	6	4.0	0.7	
1340+14.00	WB	DL	100	6	66.7	11.2	
1328+11.00	WB	DL	70	6	46.7	7.8	
1326+65.00	WB	DL	6	6	4.0	0.7	
1325+60.00	WB	DL	6	6	4.0	0.7	
1325+04.00	WB	DL	6	6	4.0	0.7	
1317+36.00	WB	DL	6	6	4.0	0.7	
SUB-TOTAL =						292.7	49.2

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\pwwork\pwwork\cear1lock\j\d0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = ceal1lockj

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 3 of 4 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.