

PAVEMENT SCHEDULE

LOCATION		LENGTH (FT)	WIDTH (FT)	HOT-MIX ASPHALT SURF. REM. BUTT-JOINT (SQ YD)	HOT-MIX ASPHALT SURF. REM. 2" (SQ YD)	HOT-MIX ASPHALT SURF. REM. (VAR. DEPTH) (SQ YD)	SHOULDER WIDTH (RT. & LT.) (FT)	SHOULDER AREA (SQ YD)	LEVELING BINDER (MM) N70 (3/4") (TON)	HMA SURF. COURSE MIX "D" N70 (1 1/2") (TON)	HMA SURF. COURSE MIX "D" N70 (2") (TON)	LEVELING BINDER (MM) N50 (3/4") (TON)	HMA SURF. COURSE MIX "C", N50 (1 1/2") (TON)	INCIDENTAL HMA SURFACE (TON)	BIT. MAT. PRIME CT. (TON)	AGG. PRIME CT. (TON)	
STATION TO STATION																	
FAP 753 (IL 104)																	
STA. 935+65.00	TO	STA. 937+02.10	137.10	30		457.0	6	91.4					51.2		0.21	1.10	
STA. 937+02.10	TO	STA. 982+05.00	4,502.90	26		13008.5						1457			4.94	26.02	
STA. 982+05.00	TO	STA. 987+86.25	581.25	44.5	173.0	2700.9	20.5	1324.0	120.8	241.6					1.60	8.40	
BRIDGE OMISSION STA 987+86.25 TO STA 989+93.75																	
STA. 989+93.75	TO	STA. 992+00.00	206.25	44.5	173.0	846.7			42.8	85.7					0.39	2.04	
STA. 992+00.00	TO	STA. 996+50.00	450.00	44.5			20.5	1025.0	93.6	187.0					1.24	6.50	
STA. 996+50.00	TO	STA. 997+00.00	50.00	32			8	44.4	7.5	15					0.08	0.44	
STATION EQUATION 997+00.00 BK = 996+73.13 AH																	
STA. 996+73.13	TO	STA. 1000+00.00	326.87	32			8	290.6	48.8	97.6					0.55	2.91	
STA. 1000+00.00	TO	STA. 1095+05.45	9,505.45	32			8	8449.3				1419.5	2839.0		16.05	84.49	
SIDEROADS																	
13 TH ST		STA. 936+91.00 LT	10.00 VAR 69.00 -41.0		61.1									6.42	0.02	0.12	
13 TH ST		STA. 937+12.00 RT	23.50 VAR 72.00 -30.0		133.2									13.98	0.05	0.27	
12 TH ST		STA. 941+28.00 LT	10.00 VAR 69.00 -39.0		60.0									6.30	0.02	0.12	
12 TH ST		STA. 941+28.00 RT	10.00 VAR 71.00 -39.0		61.1									6.42	0.02	0.12	
11 TH ST		STA. 945+49.00 LT	10.00 VAR 69.00 -37.0		58.9									6.18	0.02	0.12	
11 TH ST		STA. 945+49.00 RT	10.00 VAR 63.00 -39.0		56.7									5.95	0.02	0.11	
10 TH ST		STA. 949+55.00 LT	10.00 VAR 70.00 -40.0		61.1									6.42	0.02	0.12	
10 TH ST		STA. 949+55.00 RT	10.00 VAR 72.00 -37.0		60.6									6.36	0.02	0.12	
9 TH ST		STA. 954+91.00 LT	10.00 VAR 67.00 -39.0		58.9									6.18	0.02	0.12	
9 TH ST		STA. 954+91.00 RT	10.00 VAR 72.00 -37.0		60.6									6.36	0.02	0.12	
8 TH ST		STA. 959+72.00 LT	10.00 VAR 72.00 -39.0		61.7									6.48	0.02	0.12	
8 TH ST		STA. 959+72.00 RT	10.00 VAR 69.00 -38.0		59.4									6.24	0.02	0.12	
7 TH ST		STA. 963+03.00 LT	10.00 VAR 70.00 -37.5		59.7									6.27	0.02	0.12	
7 TH ST		STA. 963+03.00 RT	10.00 VAR 63.00 -37.5		55.8									5.86	0.02	0.11	
6 TH ST		STA. 965+74.00 LT	10.00 VAR 39.00 -39.0		43.3									4.55	0.02	0.09	
6 TH ST		STA. 965+74.00 RT	10.00 VAR 63.00 -36.5		55.3									5.80	0.02	0.11	
5 TH ST		STA. 969+66.00 LT	10.00 VAR 72.00 -38.0		61.1									6.42	0.02	0.12	
5 TH ST		STA. 969+66.00 RT	10.00 VAR 69.00 -39.0		60.0									6.30	0.02	0.12	
4 TH ST		STA. 975+12.00 LT	10.00 VAR 71.00 -42.0		62.8									6.59	0.02	0.13	
4 TH ST		STA. 975+12.00 RT	10.00 VAR 66.00 -38.5		58.1									6.10	0.02	0.12	
P. E.		STA. 997+82.00 LT	8.0 VAR 32.00 -24.0		24.9									2.61	0.01	0.05	
M. B.		STA. 997+82.00 LT	8.0 VAR 32.00 -14.0		20.4									2.15	0.01	0.04	
C. E.		STA. 1000+10.00 RT	10.0 VAR 66.00 -56.0		38.0									4.00	0.01	0.08	
C. E.		STA. 1000+69.00 RT	10.0 VAR 60.00 -50.0		34.0									3.60	0.01	0.07	
COTTON HILL RD		STA. 1001+74.00 LT	10.00 VAR 56.00 -41.0		30.0									3.15	0.01	0.06	
COTTON HILL RD		STA. 1001+74.00 RT	10.00 VAR 61.00 -41.0		31.3									3.30	0.01	0.06	
M. B.		STA. 1055+25.00 RT	8.0 AR 102.00 -76.0		34.7									3.60	0.01	0.07	
				TOTAL		1,809				313.5	626.8	1,508	1,419.5	2,839.0	154	25.6	134.9

SANGAMON COUNTY

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwwork\p\WIDOT\LAUGHLINRL\0122712\0672062-ah-t-schedule.dgn		DRAWN -	REVISED -		753	141RS-6&142RS-6	*	62	10				
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 72B13				
PLOT DATE = Feb-05-2010 11:45:38AM		DATE -	REVISED -		ILLINOIS FED. AID PROJECT				* SANGAMON, CHRISTIAN				