

PAVEMENT MARKING

LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	PAIN T PAVEMENT MARKING - LINE 5'' (FT)	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5'' (FT)
IL (104)					
YELLOW					
STA. 935+65.00 TO STA. 997+00.00	SKIP - DASH (CENTER)	6135.0	10' @ 40'		1534
STA. 993+20.00 TO STA. 997+00.00	EAST BOUND NPZ	380.0	SOLID	380	
STATION EQUATION 997+00.00 BK = 996+73.13 AH					
STA. 996+73.13 TO STA. 1095+05.45	SKIP - DASH (CENTER)	9832.3	10' @ 40'	2458	
STA. 996+73.13 TO STA. 1003+60.00	EAST BOUND NPZ	686.9	SOLID	687	
STA. 1003+60.00 TO STA. 1010+00.00	WEST BOUND NPZ	640.0	SOLID	640	
WHITE					
STA. 935+65.00 TO STA. 937+06.00	LT & RT SOLID (EDGE LINE)	141.0	-	282	
STA. 982+05.00 TO STA. 997+00.00	LT & RT SOLID (EDGE LINE)	1495.0	-	2990	
STATION EQUATION 997+00.00 BK = 996+73.13 AH					
STA. 996+73.13 TO STA. 1095+05.45	LT & RT SOLID (EDGE LINE)	9832.3	-	19665	
				TOTAL	27102
					1534

ABBREVIATIONS

N. P. Z. = NO PASSING ZONE

SHORT-TERM PAVEMENT MARKING

LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	LENGTH (FT)	WORK ZONE PAVE MARK REM (SQ FT)
IL (104)						
YELLOW						
STA. 935+65.00 TO STA. 997+00.00	SKIP - DASH (CENTER)	6135.0	4' @ 40'	3	1841	205
STATION EQUATION 997+00.00 BK = 996+73.13 AH						
STA. 996+73.13 TO STA. 1095+05.45	SKIP - DASH (CENTER)	9832.3	4' @ 40'	3	2950	328
					TOTALS	533

SHOULDER RUMBLE STRIP

LOCATION STATION TO STATION	LENGTH (FT)
IL (104)	
STA. 1002+02.00 TO STA. 1095+05.45	LEFT 9303.5
STA. 1002+05.00 TO STA. 1095+05.45	RIGHT 9300.5
TOTAL	18604

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	TWO-WAY AMBER (EACH)	REMOVAL (EACH)
IL 104			
STA. 935+65.00 TO STA. 987+86.25	5221.25	66	66
BRIDGE OMISSION STA 987+86.25 TO STA 989+93.75			
STA. 989+93.75 TO STA. 997+00.00	706.25	9	9
STATION EQUATION 997+00.00 BK = 996+73.13 AH			
STA. 996+73.13 TO STA. 1095+05.45	9832.32	123	123
		TOTALS	198

SANGAMON COUNTY

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\pwwork\PWIDOT\LAUGHLINRL\0122712\0672062-shr-schedule.dgn		DRAWN -	REVISED -			753	141RS-6&142RS-6	*	62	12	
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 72B13					
PLOT DATE = Feb-05-2010 11:45:43AM		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.