

SIDE ROAD AND ENTRANCE SCHEDULE												
LOCATION		EXIST. SURF. TYPE	WIDTH ACROSS FRONT (FT)	WIDTH ACROSS BACK (FT)	LENGTH (FROM EOP TO LIMITS OF IMPROVEMENT) (FT)	PREPARATION OF BASE (SQ YD)	HOT-MIX ASPHALT SURF. REM. BUTT-JOINT (SQ YD)	INCIDENTAL BITUMINOUS SURFACE (TON)	BIT. MAT. PRIME CT. (TON)	AGG. PRIME CT. (TON)	AGGREGATE SURFACE COURSE (TON)	
S.R. OR ENT.	STATION											
ZENOBIA RD, 6E	STA. 1094+93.21 RT.	BIT.	75.0	55.0	10.0	-	72.22	6.07	0.03	0.14		
CARDINAL HILL RD, 6E	STA. 1095+05.45 LT.	BIT.	150.0	46.5	36.0	-	393.00	33.01	0.15	0.79		
C.E.	STA. 1115+31.00 RT.	AGG.	95.0	75.0	10.0	94.44	-	42.31	0.13	-	7.12	
P.E.	STA. 1134+75.00 LT.	AGG.	40.0	24.0	8.0	28.44	-	5.58	0.04	-	3.19	
SICILY RD, 175E	STA. 1187+73.77 RT.	BIT.	68.0	28.0	28.0	-	149.33	12.54	0.06	0.30		
C.E.	STA. 1187+74.00 LT.	BIT.	40.0	20.0	10.0	-	33.33	2.80	0.01	-		
C.E.	STA. 1198+60.50 RT.	BIT.	45.0	25.0	10.0	-	38.89	3.27	0.01	-		
C.E.	STA. 1198+60.50 LT.	BIT.	80.0	48.0	15.0	-	106.67	8.96	0.04	-		
C.E./TURNLANE	STA. 1204+76.00 LT.	BIT.	ENTRANCE ADJACENT TO RIGHT TURN LANE IN GOOD CONDITION, NO WORK REQUIRED									
C.E.	STA. 1214+05.00 LT.	BIT.	55.0	26.5	18.0	-	81.50	6.85	0.03	-		
250E	STA. 1227+85.90 RT.	BIT.	100.0	29.0	35.0	-	250.83	21.07	0.10	0.50		
BOAT RAMP	STA. 1254+26.00 LT.	BIT.	82.0	19.0	57.5	-	322.64	27.10	0.12	0.65		
430E	STA. 0+04.78 LT.	AGG.	56.0	36.0	10.0	51.11	-	22.90	0.07	0.10	3.42	
430E	STA. 0+04.78 RT.	BIT.	117.0	48.0	15.0	-	137.50	11.55	0.05	0.28		
C.E.	STA. 4+96.50 RT.	BIT.	55.0	35.0	10.0	-	50.00	4.20	0.02	-		
C.E.	STA. 26+45.50 LT.	BIT.	55.0	35.0	10.0	-	50.00	4.20	0.02	-		
TOVEY RD, 465E	STA. 26+45.87 RT.	BIT.	101.0	58.5	15.0	-	132.92	11.17	0.05	0.27		
ENT.	STA. 37+74.00 LT.	AGG.	-	-	-	-	-	-	-	-		
P.E.	STA. 53+45.00 LT.	AGG.	38.0	22.0	8.0	26.67	-	5.23	0.04	-	2.92	
P.E.	STA. 53+57.00 RT.	BIT.	43.0	23.0	10.0	-	36.67	3.08	0.01	-		
P.E.	STA. 54+96.00 RT.	BIT.	38.0	16.0	11.0	-	33.00	2.77	0.01	-		
P.E.	STA. 64+64.00 LT.	BIT.	40.0	24.0	8.0	-	28.44	2.39	0.01	-		
						TOTALS	201.00	1,916.94	237.03	1.01	3.02	16.65

SHORT-TERM PAVEMENT MARKING								
LOCATION		DESCRIPTION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	LENGTH (FT)	WORK ZONE PAVE. MARK. REM. (SQ FT)	
STATION	TO STATION							
FAP 753 (IL 104)		YELLOW						
STA. 1095+05.45	TO STA. 1108+30.24	SKIP - DASH (CENTER)	1324.79	4' @ 40'	3	397	44	
BRIDGE OMISSION STA. 1108+30.24 TO STA. 1109+82.11								
STA. 1109+82.11	TO STA. 1176+74.44	SKIP - DASH (CENTER)	6692.33	4' @ 40'	3	2008	223	
BRIDGE OMISSION STA. 1176+74.44 TO STA. 1178+45.56								
STA. 1178+45.56	TO STA. 1250+67.31	SKIP - DASH (CENTER)	7221.75	4' @ 40'	3	2167	241	
BRIDGE OMISSION STA. 1250+67.31 TO STA. 1252+02.64								
STA. 1252+02.64	TO STA. 1314+63.99	SKIP - DASH (CENTER)	6261.35	4' @ 40'	3	1878	209	
STATION EQUATION STA. 1314+63.99 BK. = STA. 0+00.00 AH.								
STA. 0+00.00	TO STA. 39+98.83	SKIP - DASH (CENTER)	3998.83	4' @ 40'	3	1200	133	
BRIDGE OMISSION STA. 39+98.83 TO STA. 41+91.17								
STA. 41+91.17	TO STA. 69+95.99	SKIP - DASH (CENTER)	2804.82	4' @ 40'	3	841	93	
STATION EQUATION STA. 69+95.99 BK. = STA. 70+03.00 AH.								
STA. 70+03.00	TO STA. 79+72.00	SKIP - DASH (CENTER)	969.00	4' @ 40'	3	291	32	
						TOTALS	8782	976

PAINT PAVEMENT MARKING - LINE 5"						
LOCATION			LENGTH (FT)	WHITE (FT)	YELLOW (FT)	
STATION	TO	STATION				
IL (104)						
STA. 1095+05.45	TO	STA. 1108+30.24	1324.79	2424.58	331.20	
BRIDGE OMISSION STA. 1108+30.24 TO STA. 1109+82.11			151.87	303.74	37.97	
STA. 1109+82.11	TO	STA. 1176+74.44	6692.33	13249.66	4227.37	
BRIDGE OMISSION STA. 1176+74.44 TO STA. 1178+45.56			171.12	342.24	42.78	
STA. 1178+45.56	TO	STA. 1250+67.31	7221.75	14055.5	3821.15	
BRIDGE OMISSION STA. 1250+67.31 TO STA. 1252+02.64			135.33	270.66	169.16	
STA. 1252+02.64	TO	STA. 1314+63.99	6261.35	12440.7	2814.60	
STATION EQUATION STA. 1314+63.99 BK. = STA. 0+00.00 AH.						
STA. 0+00.00	TO	STA. 39+98.83	3998.83	7613.66	999.71	
BRIDGE OMISSION STA. 39+98.83 TO STA. 41+91.17			192.34	384.68	48.09	
STA. 41+91.17	TO	STA. 69+95.99	2804.82	5450.64	701.21	
STATION EQUATION STA. 69+95.99 BK. = STA. 70+03.00 AH.						
STA. 70+03.00	TO	STA. 79+72.00	969.00	1938	242.25	
				SUBTOTAL	58474.06	13435.47
				TOTAL	71910	

CHRISTIAN COUNTY

FILE NAME =	USER NAME = laughlir1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwwork\PWIDOT\LAUGHLIR\122712\0672062-sh-t-schedule.dgn	DRAWN -	REVISED -	753			141RS-6&142RS-6	*	62	15	
PLOT SCALE = 1/8" = 1' IN.	CHECKED -	REVISED -	CONTRACT NO. 72B13							
PLOT DATE = Feb-05-2010 11:45:50AM	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT