

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	IL 123	IL 123	IL 123	IL 123
				SANGAMON COUNTY	MENARD COUNTY	SANGAMON COUNTY	MENARD COUNTY
			100% STATE	I000	I000	SFTY-3J	SFTY-2A
				100% STATE	100% STATE	100% STATE	100% STATE
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	26.0				26.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	60.0	10.0	50.0		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	114.5	16.9	97.6		
40600300	AGGREGATE (PRIME COAT)	TON	429.6	63.5	366.1		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6331.5	935.9	5395.6		
40600895	CONSTRUCTING TEST STRIP	EACH	1.0		1.0		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2248.6	351.9	1896.7		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	40.4		40.4		
40600990	TEMPORARY RAMP	SQ YD	874.5	126.7	747.8		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12396.6	1605.4	10791.2		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	293.0	32.8	260.2		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20440.0		20440.0		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	130180.3	22153.2	108027.1		
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	1800.0	180.0	1620.0		
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	500.0	50.0	450.0		
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	500.0	50.0	450.0		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2757.7	469.0	2288.7		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	656.4				656.4
60255500	MANHOLES TO BE ADJUSTED	EACH	4.0		4.0		
63200310	GUARDRAIL REMOVAL	FOOT	25.0			25.0	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2.0			2.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12.0	2.0	10.0		
67100100	MOBILIZATION	L SUM	1.0	0.1	0.9		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.1	0.9		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.1	0.9		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0				1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0		1.0		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14848.0	2258.0	12590.0		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1650.0	251.0	1399.0		
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	18.0	9.0	9.0		
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	121594.0	16934.0	104660.0		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	620.0	95.0	525.0		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2.0			2.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	620.0	95.0	525.0		

* - SANGAMON & MENARD

FILE NAME :	USER NAME : coxte	DESIGNED -	REVISED -
et:\pwwork\pwwork\COXTE\0132883\0672018\shl-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF	SHEETS
		STA.	TO STA.

F.A.S. RTE. 1573	SECTION 10IRS-5 & 102RS-4	COUNTY *	TOTAL SHEETS 26	SHEET NO. 3
			CONTRACT NO. 72C58	
ILLINOIS FED. AID PROJECT				