

MAINLINE PAVEMENT MARKING SCHEDULE		LENGTH	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 6" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 8" WHITE	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
STATION TO	STATION												
US 50													
EAST BOUND													
806+34.43	TO 849+44.81	4310.4	4310.4	4310.4	1080.0	0.0	8620.8	1080.0	0.0	1812.0	201.3	108.0	0.0
849+44.81	TO 851+45.19	200.4	200.4	200.4	50.0	0.0	400.8	50.0	0.0	84.0	9.3	6.0	6.0
851+45.19	TO 864+38.89	1293.7	1293.7	1293.7	320.0	0.0	2587.4	320.0	0.0	540.0	60.0	32.0	0.0
864+38.89	TO 865+50.89	112.0	112.0	112.0	30.0	0.0	224.0	30.0	0.0	48.0	5.3	2.0	4.0
865+50.89	TO 935+53.19	7002.3	7002.3	7002.3	1750.0	0.0	14004.6	1750.0	0.0	2940.0	326.7	176.0	0.0
935+53.19	TO 940+06.81	453.6	453.6	453.6	110.0	0.0	907.2	110.0	0.0	192.0	21.3	12.0	12.0
940+06.81	TO 951+27.20	1120.4	1120.4	1120.4	280.0	0.0	2240.8	280.0	0.0	468.0	52.0	28.0	0.0
951+27.20	TO 955+37.45	410.3	0.0	410.3	100.0	0.0	410.3	100.0	0.0	168.0	18.7	10.0	0.0
955+37.45	TO 957+39.00	201.6	0.0	201.6	50.0	201.6	201.6	50.0	201.6	84.0	9.3	6.0	0.0
957+39.00	TO 965+60.68	821.7	821.7	821.7	210.0	0.0	1643.4	210.0	0.0	348.0	38.7	20.0	0.0
965+60.68	TO 967+66.86	206.2	206.2	206.2	50.0	0.0	412.4	50.0	0.0	84.0	9.3	6.0	6.0
967+66.86	TO 975+53.36	786.5	786.5	786.5	200.0	0.0	1573.0	200.0	0.0	336.0	37.3	20.0	0.0
975+53.36	TO 977+13.08	159.7	0.0	159.7	40.0	0.0	159.7	40.0	0.0	72.0	8.0	4.0	0.0
977+13.08	TO 984+28.27	715.2	0.0	715.2	180.0	0.0	715.2	180.0	0.0	300.0	33.3	18.0	0.0
984+28.27	TO 985+06.79	78.5	78.5	78.5	20.0	0.0	157.0	20.0	0.0	36.0	4.0	2.0	0.0
985+06.79	TO 987+15.96	209.2	209.2	209.2	50.0	0.0	418.3	50.0	0.0	84.0	9.3	6.0	6.0
987+15.96	TO 1063+65.00	7649.0	7649.0	7649.0	1910.0	0.0	15298.1	1910.0	0.0	3204.0	356.0	192.0	0.0
SHEET TOTALS			24243.9	25730.6	6430.0	201.6	49974.4	6430.0	201.6	10800.0	1199.8	648.0	34.0

• (51-24)RS-3 & (51-24-2)RS-1

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\PWIDOT\SWARTZRW\d0138979\d7	4390-sht-schudgn	DRAWN -	REVISED -					327	*	LAWRENCE	49	14
PLOT SCALE = 50,000' / IN.		CHECKED -	REVISED -		SCALE: NA			SHEET NO. 7 OF 14 SHEETS			CONTRACT NO. 74390	
PLOT DATE = 1/28/2010		DATE -	REVISED -		STA. TO STA.			ILLINOIS FED. AID PROJECT				