

PAVING SCHEDULE

MILE STATION	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	LEVELING BINDER (MACHINE METHOD), N70 (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 (TON)	LT. AGGREGATE WEDGE SHOULDERS, TYPE B (TON)	RT. AGGREGATE WEDGE SHOULDERS, TYPE B (TON)
0.0 TO 0.5	2.12	10.27	835.71	640.17	125.94	103.26
0.5 TO 1.0	2.02	9.75	646.95	593.27	107.15	106.91
1.0 TO 1.5	2.02	9.79	458.19	546.48	88.37	105.69
1.5 TO 2.0	2.05	9.90	505.53	552.52	80.74	93.55
2.0 TO 2.5	2.05	9.94	630.75	556.49	60.98	78.79
2.5 TO 3.0	2.04	9.86	646.58	552.55	56.90	73.79
3.0 TO 3.5	2.04	9.86	547.60	552.55	49.39	90.20
3.5 TO 4.0	2.07	10.01	521.67	560.68	56.51	67.94
4.0 TO 4.5	1.66	8.03	341.68	449.56	37.37	26.64
4.5 TO 5.0	1.57	7.58	328.94	424.68	48.42	30.5
5.0 TO 5.5	1.58	7.64	526.59	538.24	81.22	40.78
5.5 TO 6.0	2.20	10.65	313.18	397.37	55.01	24.00
6.0 TO 6.5	2.05	9.92	446.46	555.50	94.53	40.09
6.5 TO 7.0	2.05	9.92	702.22	555.50	148.88	50.46
7.0 TO 7.5	2.05	9.94	846.18	554.52	180.16	53.42
7.5 TO 8.0	2.07	10.03	737.17	558.80	123.31	51.61
8.0 TO 8.5	2.03	9.83	533.33	545.39	55.58	47.78
8.5 TO 9.0	2.01	9.75	462.60	556.61	50.34	49.30
9.0 TO 9.5	2.06	9.99	490.51	567.94	91.82	77.65
9.5 TO 10.0	1.97	9.55	552.31	530.11	125.46	97.12
10.0 TO 10.5	2.05	9.90	539.35	531.04	142.65	104.33
10.5 TO 11.0	2.16	10.43	456.21	560.68	94.49	99.01
11.0 TO 11.8	2.98	14.43	799.06	776.03	62.68	86.17
11.8 TO 12.5	2.93	14.17	1056.72	778.05	166.24	119.39
12.5 TO 13.0	2.03	9.81	907.75	553.29	99.18	109.77
13.0 TO 13.5	2.08	10.05	934.93	536.52	45.15	106.8
13.5 TO 14.0	2.12	10.25	854.08	525.92	47.67	99.34
14.0 TO 14.5	2.02	9.75	704.47	525.37	76.64	73.87
14.5 TO 15.0	2.07	10.03	743.54	561.91	138.19	65.91
15.0 TO 15.5	2.07	10.01	882.49	561.91	157.58	64.83
15.5 TO 16.0	1.89	9.15	813.63	518.06	145.28	58.46
16.0 TO 16.5	2.11	10.19	882.49	561.91	220.61	91.04
16.5 TO 16.7	0.85	4.13	441.24	280.96		
WIDENED AREAS AROUND STRUCTURES 031-0007, 031-0036, 031-0033, 031-0007, 031-0032, 031-0006, & 031-0005	1.27	6.15	961.35	344.43	N/A	N/A
SUBTOTAL					3114.44	2388.40
TOTAL	68.34	330.66	22027.72	18405.01	5502.84	
ROUNDED TOTALS	68	331	22028	18405	5503	

NOTE: QUANTITIES HAVE BRIDGE OMISSIONS CALCULATED INTO THEM
 NOTE: AGGREGATE WEDGE, TYPE B QUANTITIES HAVE BRIDGE, SIDEROAD, AND ENTRANCE OMISSIONS CALCULATED INTO THEM

FILE NAME =	USER NAME = watersle	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
a:\pw_work\p\dot\watersle\d0174276\d876d70-ahp-plan.dgn	DRAWN -	REVISED -	739			501, 502 RS-5	GREENE	19	11	
PLOT SCALE = 1/8" = 1' IN.	CHECKED -	REVISED -	CONTRACT NO. 76D70							
PLOT DATE = 3/18/2010	DATE -	REVISED -	FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT							
					SCALE: _____	SHEET NO. 6 OF 8 SHEETS		STA. _____ TO STA. _____		