

HMA SURFACE REMOVAL-BUTT JOINT AND TEMP. RAMP SCHEDULE

MILE STATION	LOCATION DESCRIPTION	WIDTH (FT.)	HMA SURFACE REMOVAL-BUTT JOINT (SY.)	TEMPORARY RAMP (SY.)
0.0	BEGINNING OF JOB	64	0.0	35.6
0.0	75' NORTH OF BEG. OF JOB	23	0.0	12.8
1.3 RT	SIDEROAD 1300N	38	84.4	55.7
2.3 LT	SIDEROAD 2300N	56	124.4	82.1
2.6 RT	UNKNOWN SIDEROAD	54	120.0	79.2
4.1	SN. 031-0011 S. APP.	22	73.3	12.2
4.1	SN. 031-0011 N. APP.	22	73.3	12.2
4.5	SN. 031-0010 S. APP.	22	73.3	12.2
4.5	SN. 031-0010 N. APP.	22	73.3	12.2
4.6 LT	UNKNOWN SIDEROAD	78	173.3	114.4
5.1 RT	ROAD TO HAYPRESS	53	117.8	77.7
5.5	SN. 031-0037 S. APP.	30	100.0	16.7
5.5	SN. 031-0037 N. APP.	27.5	91.7	15.3
5.7	SN. 031-0036 S. APP.	28	93.3	15.6
5.7	SN. 031-0036 N. APP.	28	93.3	15.6
5.8 RT	UNKNOWN SIDEROAD	58	128.9	85.1
7.3 RT	SIDEROAD 1900N	65	144.4	95.3
8.2	SN. 031-0033 S. APP.	40.5	135.0	22.5
8.2	SN. 031-0033 N. APP.	41.5	138.3	23.1
8.7 RT	SIDEROAD 2050N	45	100.0	66.0
8.7 LT	UNKNOWN SIDEROAD	35	77.8	51.3
9.8 RT	SIDEROAD 2160N	72	160.0	105.6
9.9	SN. 031-0032 S. APP.	36.5	121.7	20.3
9.9	SN. 031-0032 N. APP.	36	120.0	20.0
10.3 LT	UNKNOWN SIDEROAD	52	115.6	76.3
11.3 RT	UNKNOWN SIDEROAD	65	144.4	95.3
11.6	SN. 031-0006 S. APP.	30.5	101.7	16.9
11.6	SN. 031-0006 N. APP.	30.5	101.7	16.9
12.0 RT	SIDEROAD 2360N	110	244.4	161.3
12.5 LT	UNKNOWN SIDEROAD	54	120.0	79.2
13.8 LT	UNKNOWN SIDEROAD	40	88.9	58.7
13.9 LT	UNKNOWN SIDEROAD	46	102.2	67.5
14.0	SN. 031-0005 S. APP.	40	133.3	22.2
14.0	SN. 031-0005 N. APP.	39	130.0	21.7
15.4 RT	SIDEROAD 2675N	33	73.3	48.4
15.6	SN. 031-0003 S. APP.	24	80.0	13.3
15.6	SN. 031-0003 N. APP.	24	80.0	13.3
15.7 RT	SIDEROAD 2710N	48	106.7	70.4
15.7 RT	SIDEROAD 2710N	35	77.8	51.3
16.7	END OF JOB	24	80.0	13.3
SUBTOTAL			4197.5	1849.1
RD. TOTAL			4198	1849

NOTE: BUTT JOINTS AT SIDEROADS ARE 20' LONG AND 30' LONG AT ALL STRUCTURES AND AT THE END OF THE JOB
 NOTE: TEMP. RAMPS AT SIDEROADS ARE 13.2' LONG AND 5' LONG AT ALL STRUCTURES AND THE BEGINNING AND END OF THE JOB

FILE NAME =	USER NAME = watersle	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw\work\p\idot\watersle\d0174276\d876	d70-sht-plan.dgn	DRAWN -	REVISED -			739	501, 502 RS-5	GREENE	19	12	
	PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	REVISED -					CONTRACT NO. 76D70			
	PLOT DATE = 3/18/2010	DATE -	REVISED -			SCALE: _____	SHEET NO. 7 OF 8 SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. 8 [ILLINOIS] FED. AID PROJECT		