

# SUMMARY OF QUANTITIES

*100% STATE*

*100% STATE*

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	-----	-----	CODE NO	ITEM	UNIT		-----	-----	-----
20200100	EARTH EXCAVATION	CU YD	2305	2305		*72000200	SIGN PANEL - TYPE 2	SQ FT	16	16			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25	25		*X7800200	PAINT PAVEMENT MARKING CURB	FOOT	25	25			
40600300	AGGREGATE (PRIME COAT)	TON	117	117		Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3264	3264									
40600895	CONSTRUCTING TEST STRIP	EACH	1	1									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	747	747									
40600990	TEMPORARY RAMP	SQ YD	435	435									
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	6601	6601									
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	36517	36517									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	62214	62214									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1728	1728									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	12215	12215									
67100100	MOBILIZATION	L SUM	1	1									
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1									
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7970	7970									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80369	80369									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	88	88									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	95	95									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2656	2656									
*73000100	WOOD SIGN SUPPORT	FOOT	16	16									
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123									
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	80369	80369									
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	88	88									
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	95	95									
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	401	401									
*78200300	PRISMATIC CURB REFLECTOR	EACH	11	11									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	683	683									

*\*Specialty Items*

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.S. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			2780	128 RS-2	CLINTON	14	4	
PLOT SCALE = #SCALE#		CHECKED -	REVISED -			SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____					
PLOT DATE = #DATE#		DATE -	REVISED -			FED. ROAD DIST. NO. _____ [ILLINOIS] FED. AID PROJECT					

CONTRACT NO. 76D82