

CONSTRUCTION TYPE CODE	
FULTON CO.	
100% STATE	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3775	3775	
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	355	355	
35501308	HOT - MIX ASPHALT BASE COURSE, 6"	SQ YD	4358	4358	
35600716	HOT - MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	2850	2850	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	2043	2043	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	112	112	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	29.9	29.9	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2455	2455	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	303	303	
40600990	TEMPORARY RAMP	SQ YD	183	183	
40603000	HOT - MIX ASPHALT BINDER COURSE, IL - 12.5, N50	TON	3189	3189	
40603535	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4922	4922	
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	529	529	

FILE NAME = miscellaneous_sheets.dgn

USER NAME = jochumejg
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = 3/22/2010

DESIGNED - KJH	REVISED -
DRAWN - JGJ	REVISED -
CHECKED - KJH	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	16W-2,RS-4;17W-1,RS-3	FULTON	240	12
CONTRACT NO. 88703			ILLINOIS FED. AID PROJECT	