

CONSTRUCTION TYPE CODE	
FULTON CO.	
100% STATE	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	
54215562	METAL END SECTIONS 27"	EACH	2	2	
54215565	METAL END SECTIONS 30"	EACH	2	2	
54248510	CONCRETE COLLAR	CU YD	12.5	12.5	
542A0232	PIPE CULVERTS, CLASS A, TYPE 1 27"	FOOT	68	68	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	120	120	
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	64	64	
542A1927	PIPE CULVERTS, CLASS A, TYPE 3 42"	FOOT	129	129	
542A1969	PIPE CULVERTS, CLASS A, TYPE 3 84"	FOOT	50	50	
542A2767	PIPE CULVERTS, CLASS A, TYPE 4 42"	FOOT	62	62	
542A2779	PIPE CULVERTS, CLASS A, TYPE 4 54"	FOOT	56	56	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	1306	1306	
542D0226	PIPE CULVERTS, CLASS D, TYPE 1 21"	FOOT	286	286	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	140	140	
542D0232	PIPE CULVERTS, CLASS D, TYPE 1 27"	FOOT	66	66	

FILE NAME = miscellaneous_sheets.dgn

USER NAME = jochumsjg
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = 3/22/2010

DESIGNED - KJH	REVISED -
DRAWN - JGJ	REVISED -
CHECKED - KJH	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 7 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	16W-2,RS-4;17W-1,RS-3	FULTON	240	16
CONTRACT NO. 88703			ILLINOIS FED. AID PROJECT	