

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE										
CODE NO	ITEM	UNIT	TOTAL						CODE NO	ITEM	UNIT	TOTAL											
			QUANTITIES	1000									QUANTITIES	1000									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15							70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2128	2128								
40600300	AGGREGATE (PRIME COAT)	TON	74	74							70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	275	275								
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4							70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	46	46								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1347	1347								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	455	455							* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	21	21								
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	270	270							* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2128	2128								
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	132	132							* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	275	275								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3203	3203							* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	46	46								
42001300	PROTECTIVE COAT	SQ YD	419	419							* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	52	52								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	87	87							78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	52	52								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	25	25							88600600	DETECTOR LOOP REPLACEMENT	FOOT	876	876								
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20440	20440							X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	87	87							X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1417	1417								
44000600	SIDEWALK REMOVAL	SQ FT	25	25							X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	4514	4514								
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1480	1480							Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	51	51								
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	588	588																			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	536	536																			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	260	260																			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	60	60																			
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100																			
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	36	36																			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	54	54																			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																			
67100100	MOBILIZATION	L SUM	1	1																			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1																			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4041	4041																			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	21	21																			

FILE NAME = USER NAME = drvkoksgn  
 22\pwr\work\FM\DOT\DRIVAKOSGN\00136803\0134899-1\plan.dgn  
 PLOT SCALE = 50.000' / IN.  
 PLOT DATE = 4/14/2009

DESIGNED - REVISED -  
 DRAWN - REVISED -  
 CHECKED - REVISED -  
 DATE - REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.  
 2761 0102RS-6 COOK 28 3  
 CONTRACT NO. 60663  
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT