

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE: I000-2A						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE: I000-2A						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
				I000										I000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1	1						* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	78	78				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70				
40600300	AGGREGATE (PRIME COAT)	TON	28	28						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	21	21				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	2	2						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	40	40				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	296	296						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.04	51.04				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	99	99						XX002258	STRUCTURES TO BE ADJUSTED	EACH	1	1				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	154	154														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	592	592														
42001300	PROTECTIVE COAT	SQ YD	112	112														
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	7044	7044														
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300														
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	915	915														
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	395	395														
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	42	42														
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	478	478														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	126	126														
60600605	CONCRETE CURB, TYPE B	FOOT	100	100														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2														
67100100	MOBILIZATION	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	468	468														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4816	4816														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	283	283														
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	78	78														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70														
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78														
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4816	4816														
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	283	283														

\* Specialty Items

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FILE NAME =	USER NAME =	DESIGNED -	REVISED -					F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\rodri\rodri\0125805\106406-str-pln\rdgn	rodri	DRAWN -	REVISED -					2775	0101 RS-4	COOK	17	3
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -					CONTRACT NO. 60A51				
PLOT DATE = 4/23/2009		DATE -	REVISED -					SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT	