

100% STATE I000

SUMMARY OF QUANTITIES			TOTAL	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	QUANTITIES	URBAN	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13504	13504	
40600300	AGGREGATE (PRIME COAT)	TON	271	271	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	587	587	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	228	228	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,672	5,672	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	167	167	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	66,931	66,931	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	28	28	
44000600	SIDEWALK REMOVAL	SQ FT	167	167	
44001700	COMBINATION <sup>CONCRETE</sup> CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	555	555	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,353	1,353	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	68	68	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	203	203	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	406	406	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	676	676	
55039700	STORM SEWERS TO BE CLEANED	FOOT	105	105	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	7	7	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	33	33	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12,284	12,284	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	546	546	

100% STATE I000

SUMMARY OF QUANTITIES			TOTAL	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	QUANTITIES	URBAN	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24,567	24,567	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,985	2,985	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,000	1,000	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	465	465	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	356	356	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	546	546	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24,567	24,567	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,985	2,985	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,000	1,000	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	465	465	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	356	356	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,023	1,023	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	767	767	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	115	115	
88600600	DETECTOR LOOP REPLACEMENT	FOOT	<b>2,287</b>	<b>2,287</b>	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154	154	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,545	3,545	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

\* SPECIALTY ITEM