SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	130	130					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50	50					
40600300	AGGREGATE (PRIME COAT)	TON	249	249					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	32	32					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	270	270					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	11	11					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5225	5225					
42001300	PROTECTIVE COAT	SQ YD	25	25					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	62200	62200					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	355	355					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	100	100					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	150	150					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	260	260					
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	12	12					
60404940	FRAMES AND GRATES, TYPE 23	EACH	10	10					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8715	8715					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	270	270					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46825	46825					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1300	1300					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	830	830					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	420	420					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	21705	21705					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	270	270					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46825	46825					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1300	1300					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	830	830					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	420	420					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	420	420					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	350	350					
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2					
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2480	2480					
	87900200	DRILL EXISTING HANDHOLE	EACH	14	14					
	88500100	INDUCTIVE LOOP DETECTOR	EACH	8	8					
	88600100	DETECTOR LOOP, TYPE I	FOOT	495	495					
	88600600	DETECTOR LOOP REPLACEMENT	FOOT	780	780					
	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2175	2175					
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2450	2450					
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	32	32					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\smithkl\d137142\D123406-sht-plan.dgn	USER NAME = smithkl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN -	REVISED -	
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -	
	PLOT DATE = 4/23/2009	DATE -	REVISED -	

SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2845	(34&75) RS-4	COOK	28	3

CONTRACT NO. 60B05

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT