

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	1000								CODE NO	ITEM	UNIT	1000														
20201006	GRADING AND SHAPING SHOULDERS	UNIT	266	266							70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50	50							70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9621	9621													
40600300	AGGREGATE (PRIME COAT)	TON	243	243							70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	378	378													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	37	37							70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	42358	42358													
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	853	853													
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	414	414							70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	182	182													
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	120	120							70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	113	113													
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5086	5086							70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	214	214													
42001300	PROTECTIVE COAT	SQ YD	67	67							70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3207	3207													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	60543	60543							* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	378	378													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300							* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42358	42358													
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	711	711							* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	853	853													
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	20	20							* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	182	182													
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	400	400							* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	113	113													
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	110	110							* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	214	214													
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	160	160							* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	319	319													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	900	900							78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	319	319													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	28	28							* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	405	405													
60300410	VALVE BOX FRAMES TO BE ADJUSTED WITH NEW FRAMES	EACH	4	4							X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6							X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2384	2384													
67100100	MOBILIZATION	L SUM	1	1							Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1							Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1													

*Specialty Items

FILE NAME =	USER NAME = ulr10hkd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				IL. RTE. 132 (IL. RTE. 59 TO SHERMAN DR.) SUMMARY OF QUANTITIES				F.A.P. RTE. 514	SECTION W-RS-3	COUNTY LAKE	TOTAL SHEETS 23	SHEET NO. 3
CONTRACT NO. 60B55	PLOT SCALE = 50,000' / IN.	CHECKED -	REVISED -									SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	
	PLOT DATE = 3/30/2009	DATE -	REVISED -													