SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	25	5				
40600300	AGGREGATE (PRIME COAT)	TON	150	124	26				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	19	4				
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1250	1250					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6248	5184	1064				
42001300	PROTECTIVE COAT	SQ YD	2062	1649		413			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	74380	61715	12665				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5577	4461		1116			
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	765	573		192			
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	1132	849		283			
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1315	986		329			
55039700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	68	68					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	15	15					
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	40	40					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	129	129					
60404800	FRAMES AND GRATES, TYPE 11	EACH	1	1					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	38	38					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	21	21					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5		0.5			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.5		0.5			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5		0.5			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5070	5070					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	337	337					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9053	9053					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7572	7572					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
				1000	1000	1000			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1508	1508					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	379	379					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	940	940					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10970	10970					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	337	337					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9053	9053					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7572	7572					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1508	1508					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	379	379					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	940	940					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	377	377					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	320	320					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1045	1045					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	207	207					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2929	2430	499				
~~44004600~~	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	8787	8787					
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	85	85					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	330			330			

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pw1dot\steedpa\d0100515\D137306-sht plan.dgn	USER NAME = steedpa	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/2/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MONTROSE AVE.--FOREST PRESERVE RD. TO PULASKI RD.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1366	0101 RS-5	COOK	34	3

CONTRACT NO. 60B60

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT