

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
20200700	EXCAVATING AND GRADING EXISTING SHOULDER, SPECIAL	UNIT	116	116
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33	33
40600300	AGGREGATE (PRIME COAT)	TON	87	87
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	650	650
X4060466	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90, RUBBER MODIFIED	TON	4,242	4,242
42001300	PROTECTIVE COAT	SQ YD	43	43
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	200	200
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	43,286	43,286
44000600	SIDEWALK REMOVAL	SQ FT	200	200
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1000	1000
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	550	550
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	300	300
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	2,600	2,600
48101200	AGGREGATE SHOULDERS, TYPE B	TON	869	869
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,500	2,500
60260100	INLETS TO BE ADJUSTED	EACH	5	5
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	30	30
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE I FRAME, OPEN LID	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,000	11,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	828	828
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	67,000	67,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,000	4,000
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200	200
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,000	1,000
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	800	800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,670	3,670
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	414	414
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33,500	33,500
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,000	2,000
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	100	100
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500	500
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	400
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	550	550
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	550	550
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,563	1,563
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,818	1,818
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	70	70
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	80	80

\* SPECIALTY ITEM

FILE NAME = D162E27-shr-S00.dgn  
PLOT DATE = 3/20/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	K.R.K.	REVISED -	
DRAWN -	A.C.S.	REVISED -	
CHECKED -	S.J.P.	REVISED -	
DATE -	MARCH 20, 2009	REVISED -	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
KENSINGTON ROAD

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 35+88 TO STA. 155+75

F.A.U. RTE. 1295	SECTION 0305 RS-1	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 60E27

Ra.