

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	54	54			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8			
40600300	AGGREGATE (PRIME COAT)	TON	42	42			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	381	381			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1798	1798			
42001300	PROTECTIVE COAT	SQ YD	46.7	46.7			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	22199	22199			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	140	140			
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	116	116			
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	20	20			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	214	214			
55039700	STORM SEWERS TO BE CLEANED	FOOT	300	300			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1275	1275			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16988	16988			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	264	264			

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	617	617			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	87	87			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8468	8468			
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182			
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16988	16988			
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	264	264			
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	617	617			
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	87	87			
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	196	196			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	130	130			
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	464	464			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	876	876			

• SPECIALTY ITEMS

FILE NAME: c:\pwork\PWIDOT\CALBANNB\d0107	USER NAME: galbannb 599@sh_rdw.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	IL. RTE. 53 (MADISON STREET TO BRYANT AVENUE) SUMMARY OF QUANTITIES				F.A.P. RTE. 870	SECTION 533 X-RS-5	COUNTY DUPAGE	TOTAL SHEETS 25	SHEET NO. 3
PLOT SCALE 50,0000' / IN.	PLOT DATE= 3/30/2009	CHECKED - DATE -	REVISED - REVISED -					SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 60E71	