

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	70	70
40600300	AGGREGATE (PRIME COAT)	TON	400	400
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	60	60
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	880	880
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9,841	9,841
42001300	PROTECTIVE COAT	SQ YD	214	214
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	20	20
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	393	393
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	1,068	1,068
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	99,353	99,353
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	20
44000600	SIDEWALK REMOVAL	SQ FT	393	393
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	453	453
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	100	100
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	1,800	1,800
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	240	240
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	1,260	1,260
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	30	30
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	100	100
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	40	40
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	30	30
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,090	2,090
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	109	109
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2
60403700	LIDS, TYPE 1, OPEN LID	EACH	2	2
60403800	LIDS, TYPE 1, CLOSED LID	EACH	2	2
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	51,000	51,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,586	1,586
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	34,000	34,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9,400	9,400
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,950	2,950
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,450	2,450
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,041	1,041
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7,400	7,400
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,586	1,586
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34,000	34,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9,400	9,400
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2,950	2,950
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,450	2,450
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,041	1,041
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,325	1,325
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,046	1,046
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4,326	4,326
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,173	4,173
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	190	190

* SPECIALTY ITEM

FILE NAME = D168F26-ahv-S00.dgn
PLOT DATE = 3/31/2009

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	MARCH 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
US 14 (DEMPSTER STREET) GRACE AVE. TO ILL 43 (WAUKEGAN RD.)
SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 101+93 TO STA. 209+14

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1324	3228 D-Z-Y-RS-1	COOK	32	3
CONTRACT NO. 60F26				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				