



PI POINTS U.S. RTE. 14 (DEMPSTER AVE.)						CONTROL POINTS U.S. RTE. 14 (DEMPSTER AVE.)					
POINT NO.	STATION	OFFSET	NORTHING	EASTING	DESCRIPTION	POINT NO.	STATION	OFFSET	NORTHING	EASTING	DESCRIPTION
A21	100+00.00	0	9951.8817	9761.1713	PI	1	102+39	-47.31	10000.0000	10000.0000	X-CUT
A22	120+56.65	0	9958.8236	11817.8086	PI	2	109+06	-45.06	10000.0000	10667.4600	X-CUT
A23	127+21.71	0	9960.4038	12482.8638	PI	3	113+83	34.09	9922.4600	11144.2800	PK NAIL
A24	141+00.41	0	9965.9194	13861.5596	PI	4	110+28	-52.96	10008.3100	10789.3200	GPS
A25	145+82.41	0	9968.6484	14343.5536	PI	5	119+00	28.97	9929.3200	11661.1700	PK NAIL
A26	189+24.92	0	9992.4223	18685.9938	PI	6	122+65	36.25	9923.0700	12026.6900	PK NAIL
A27	211+76.19	0	9941.3860	20936.6839	PI	7	133+46	-56.07	10018.9700	13107.0300	X-CUT
						8	136+28	57.50	9906.5300	13389.5000	X-CUT
						9	140+20	-56.80	10022.3900	13780.4900	X-CUT
						10	142+40	45.18	9921.5300	14001.1200	X-CUT
						11	145+71	45.54	9923.0400	14332.5900	X-CUT
						12	149+55	-45.84	10016.5300	14716.2500	X-CUT
						13	153+00	46.94	9925.6400	15061.0500	X-CUT
						14	162+28	46.34	9931.3200	15989.1600	X-CUT
						15	167+48	-45.64	10026.1500	16508.9400	X-CUT
						16	173+05	44.45	9939.1000	17065.9200	X-CUT
						17	176+30	48.88	9936.4500	17391.2300	X-CUT
						18	182+88	50.45	9938.4800	18048.8800	X-CUT
						19	188+59	-63.25	10055.3100	18619.7500	X-CUT
						20	194+61	59.57	9920.7100	19220.5000	X-CUT
						21	202+23	-50.23	10013.2200	19984.4100	X-CUT
						22	204+99	-50.90	10007.6200	20261.0600	X-CUT
						23	208+22	-50.28	9999.6800	20584.1800	X-CUT