SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	366	366					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	15	15					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	89	89					
25000210	SEEDING, CLASS 2A	ACRE	0.02	0.02					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1.2	1.2					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1.2	1.2					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1.2	1.2					
25100630	EROSION CONTROL BLANKET	SQ YD	89	89					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28					
40600300	AGGREGATE (PRIME COAT)	TON	140	140					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10.5	10.5					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	125	125					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2942	2942					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	35028	35028					
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	100	100					
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1337	1337					
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	1200	1200					
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	1578	1578					
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	88	88					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	506	506					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4					
63200310	GUARDRAIL REMOVAL	FOOT	200	200					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6570	6570					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	363	363					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	35593	35593					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	713	713					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	464	464					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	204	204					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	727	727					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	363	363					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35593	35593					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	713	713					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	464	464					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	204	204					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	330	330					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	198	198					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1070	1070					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1380	1380					

* specialty Items

FILE NAME = c:\pw_work\pwidot\abebowd\dms89013\sh_rdwy.dgn	USER NAME = abebowd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/18/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. ROUTE 22 (S. KRUEGER RD. – OLD MCHENRY RD.)
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20 RS-2	LAKE	20	3
		CONTRACT NO. 60F31		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT