

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30
40600300	AGGREGATE (PRIME COAT)	TON	170	170
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	600	600
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	461	461
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,586	3,586
42001300	PROTECTIVE COAT	SQ YD	566	566
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,629	1,629
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	35,221	35,221
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	7,225	7,225
44000600	SIDEWALK REMOVAL	SQ FT	1,629	1,629
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,271	1,271
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	2,350	2,350
44003100	MEDIAN REMOVAL	SQ FT	712	712
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	60	60
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	35	35
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	56	56
44213100	PAVEMENT FABRIC	SQ YD	91	91
44213200	SAW CUTS	FOOT	500	500
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	80	80
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,300	1,300
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	180	180
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	320	320
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	40	40
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	425	425
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	50	50
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	280	280
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	1,830	1,830
45200300	JOINT OR CRACK FILLING	POUND	170	170
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,350	2,350
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	80	80

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
60404700	FRAMES AND GRATES, TYPE 10	EACH	2	2
60404800	FRAMES AND GRATES, TYPE 11	EACH	2	2
60404900	FRAMES AND GRATES, TYPE 12	EACH	2	2
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2
60624600	CORRUGATED MEDIAN	SQ FT	712	712
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16,000	16,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21,960	21,960
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,842	1,842
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	466	466
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	374	374
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	262	262
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,200	2,200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,960	21,960
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,842	1,842
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	466	466
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	374	374
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	262	262
78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	770	770
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	714	714
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	276	276
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	577	577
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	40	40
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	18	18
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,783	1,783
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	246	246
Z0017202	DOWEL BARS 1 1/2"	EACH	176	176
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	71	71
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

FILE NAME = D168F43-ht-500.dgn
PLOT DATE = 4/3/2009

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - G.F.L.
DRAWN - J.V.
CHECKED - M.P.
DATE - MARCH, 2009

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL RTE. 137 (SHERIDAN ROAD)
SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 14+86 TO STA. 98+94

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
352	113 R (2&4) RS	LAKE	24	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60F43	