

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
20200100	EARTH EXCAVATION	CU YD	100	100	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	210	210	
35800200	AGGREGATE BASE REPAIR	TON	125	125	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46	46	
40600300	AGGREGATE (PRIME COAT)	TON	240	240	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	60	60	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10	10	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	480	480	
40600990	TEMPORARY RAMP	SQ YD	700	700	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	280	280	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,100	5,100	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	58,600	58,600	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,600	1,600	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	120	120	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	700	700	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	220	220	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	350	350	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	450	450	
55039700	STORM SEWER TO BE CLEANED	FOOT	600	600	
60262700	INLETS TO BE RECONSTRUCTED	EACH	4	4	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10	
64200105	SHOULDER RUMBLE STRIP	FOOT	1,750	1,750	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,400	2,400	
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,380	1,380	
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	57,400	57,400	
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7,500	7,500	
* 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,230	1,230	
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,650	1,650	
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,320	1,320	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18,100	18,100	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	460	460	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	43,900	43,900	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,500	2,500	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	410	410	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	550	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	440	440	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	600	600	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	570	570	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,900	1,900	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,170	3,170	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10	

FILE NAME = N:\PROJ\3388\3388.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wlcaster	DESIGNED MWR	REVISED -
	DRAWN MWR	REVISED -
PLOT SCALE = 1/8" = 1' / IN.	CHECKED WBL	REVISED -
PLOT DATE = 4/2/2009	DATE 4/2/09	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GALENA BOULEVARD  
IL 56 (BUTTERFIELD ROAD) TO CANTERBURY ROAD  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 22 SHEETS STA. TO STA.

F.A.U. RTE. 1521	SECTION W-RS-4	COUNTY KANE	TOTAL SHEETS 22	SHEET NO. 3
CONTRACT NO. 60F45			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	