

PROJECT BEGINS  
STA. 10+18

PROP. HOT MIX ASPHALT SURFACE REMOVAL (2 1/4") - (TYP.)  
PROP. POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50 (3/4")  
PROP. HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50 (1 1/2") - (TYP.)  
**KEMMAN AVE.**

RICHMOND AVE.  
PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 24" STOP BAR, WHITE - (TYP.)

SHAWMUT AVE.

10+00

15+00

20+00


MATCHLINE STA. 24+00

PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 4" DOUBLE SOLID, YELLOW - (TYP.) (11" C-C)

SOUTHVIEW AVE.

FAIRVIEW AVE.

PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 6" SOLID, WHITE - (TYP.)



WOODLAWN AVE.  
PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 24" STOP BAR, WHITE - (TYP.)

**KEMMAN AVE.**

PROP. HOT MIX ASPHALT SURFACE REMOVAL (2 1/4") - (TYP.)  
PROP. POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50 (3/4")  
PROP. HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50 (1 1/2") - (TYP.)

MATCHLINE STA. 24+00

25+00

30+00

35+00

MATCHLINE STA. 38+00

PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 4" DOUBLE SOLID, YELLOW - (TYP.) (11" C-C)

GRANT AVE.

LINCOLN AVE.

PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 4" DOUBLE SOLID, YELLOW - (TYP.) (11" C-C)

NOTES:  
LIMIT OF RESURFACING ON SIDE-STREETS THROUGH OUT THE IMPROVEMENT SHALL BE TO THE RADIUS OF RETURN OR AS DIRECTED BY THE ENGINEER.  
ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC (OF THE EXTRUDED TYPE) AND SHOULD BE PLACED IN ACCORDANCE WITH "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" DETAIL, (TC-13).  
ALL RAISED REFLECTIVE PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH THE DISTRICT ONE "TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKER DETAIL," (TC-11).

FILE NAME = c:\pwork\pwidot\BANKSL\dms89376\sh...dgn	USER NAME = banksl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ROADWAY AND PAVEMENT MARKING PLAN KEMMAN AVE. (SHAWMUT AVE. - 31ST STREET)</b>	F.A.U. RTE. 2714	SECTION 0404 RS-10	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 5	
PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -	SCALE: 1"=50'			SHEET NO. 1 OF 1 SHEETS	STA. 10+00 TO STA. 38+00	CONTRACT NO. 60F46		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
PLOT DATE = 3/25/2009	DATE -	REVISED -									