

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE										
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN	WILL	COOK					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN	WILL	COOK						
				100% STATE	COUNTY	COUNTY									1000	1000	1000					1000	1000
20201006	GRADING AND SHAPING SHOULDERS	UNIT	640		460	180					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	960		960							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	78		60	18					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	620		370	250						
40600300	AGGREGATE (PRIME COAT)	TON	385		299	86					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	105		105							
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49		38	11					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	28495		20545	7950						
40600895	CONSTRUCTING TEST STRIP	EACH	2		1	1					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	255		255							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	245		205	40					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	73750		52960	20790						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	312		312						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	960		960							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8090		6275	1815					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	620		370	250						
42001300	PROTECTIVE COAT	SO YD	50		25	25					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105		105							
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	96280		74710	21570					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1000		770	230						
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200		100	100					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	865		665	200						
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	1858		1858						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	749		749							
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	329		329						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4		25.7	25.7						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	823		823						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3795		2945	850						
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	494		494						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15		10	5						
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	316		316																		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	791		791																		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	475		475																		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	197			197																	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	492			492																	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	295			295																	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1275		915	360																	
55039700	STORM SEWERS TO BE CLEANED	FOOT	70		20	50																	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15		10	5																	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		3	3																	
67100100	MOBILIZATION	L SUM	1		0.7	0.3																	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		0.7	0.3																	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		0.7	0.3																	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7045		4735	2310																	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	255		255																		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	73750		52960	20790																	

* SPECIALTY ITEMS