SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	86	86					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24					
40600300	AGGREGATE (PRIME COAT)	TON	117	117					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	305	305					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2453	2453					
42001300	PROTECTIVE COAT	SQ YD	154	154					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	29191	29191					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	460	460					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	760	760					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	195	195					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1030	1030					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	400	400					
55039700	STORM SEWERS TO BE CLEANED	FOOT	300	300					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3					
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	8	8					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4325	4325					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125	125					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	22370	22370					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE ROADWAY 1000					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	875	875					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	625	625					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	200	200					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1450	1450					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125	125					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22370	22370					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	875	875					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	625	625					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	275	275					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	275	275					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1199	1199					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	40	40					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1150	1150					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	14	14					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\PWIDOT\KELLERS\d0120833\D108109-sht-plan.dgn	USER NAME = keller	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/23/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WOLF RD. (CAMP MCDONALD RD. TO MARQUARDT DR.)
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2692	2008-065 RS	COOK	26	3

CONTRACT NO. 60F50

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT