

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	35	35
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	25	25
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56	56
40600300	AGGREGATE (PRIME COAT)	TON	290	290
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	72	72
40600535	LEVELING BINDER (HAND METHOD), N70	TON	30	30
40600895	CONSTRUCTING TEST STRIP	EACH	4	4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,280	1,280
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7,300	7,300
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	2,800	2,800
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	71,900	71,900
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	40	40
44000600	SIDEWALK REMOVAL	SQ FT	2,800	2,800
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,300	1,300
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	100	100
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	860	860
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	470	470
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	300	300
55039700	STORM SEWERS TO BE CLEANED	FOOT	3,700	3,700
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	225	225
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
67100100	MOBILIZATION	L SUM	1	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,880	4,880
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	6,300	6,300
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	88,200	88,200
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	24,900	24,900
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,100	1,100
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3,300	3,300
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,300	3,300
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	19,600	19,600
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,100	2,100
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29,400	29,400
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8,300	8,300
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	350	350
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,100	1,100
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,100	1,100
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	960	960
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	920	920
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,200	3,200
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,900	3,900
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	200	200

FILE NAME = N:\PROJ\3368\3368.II\Design\ProposedPlan\3368.II-03-Quantities.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alew	DESIGNED AL	REVISED -
	DRAWN RJR	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED WBL	REVISED -
PLOT DATE = 4/8/2009	DATE 03/27/09	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROOSEVELT ROAD  
IL 171 (1ST AVENUE) TO AUSTIN BOULEVARD  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 27 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	2009-035 RS	COOK	27	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G36	