

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000						CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	200	200					
40600300	AGGREGATE (PRIME COAT)	TON	107	107						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	450	450					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	231.3	231.3					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1050	1050					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2238	2238						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1					
42001300	PROTECTIVE COAT	SQ YD	42	42															
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	26642	26642															
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	125	125															
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	235	235															
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	80	80															
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1530	1530															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	35238	35238															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	260	260															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	189	189															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	197	197															
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35238	35238															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	260	260															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	189	189															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	197	197															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	240	240															

* SPECIALTY ITEMS