

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	10	10	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	265	265	
40600300	AGGREGATE (PRIME COAT)	TON	265	265	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	820	820	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	854	854	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	12910	12910	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	131700	131700	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1220	1220	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	3330	3330	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	350	350	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1600	1600	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	980	980	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	400	400	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	40	40	
55039700	STORM SEWERS TO BE CLEANED	FOOT	4590	4590	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	37	37	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	72	72	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
* 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15600	15600	
* 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	600	600	
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	69500	69500	
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4650	4650	
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1550	1550	
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1350	1350	

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY	
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5200	5200	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	600	600	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	69500	69500	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4650	4650	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1550	1550	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1350	1350	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2874	2874	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2874	2874	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3851	3851	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	156	156	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5540	5540	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	184	184	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* SPECIALTY ITEM

P:\2007\ME07080.Var\Var_Phil\Cadd\W015_IL43\Shs\03500aht-sh-t-IL43.dgn
 USER: NAME
 MILLENNIA PROFESSIONAL SERVICES



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.8110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN	REVISED -
DRAWN - TVN	REVISED -
CHECKED - RPD	REVISED -
DATE - 4/22/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 43
IL RTE 22 (HALF DAY RD) TO ATKINSON RD

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 2706	SECTION 29RS-4	COUNTY LAKE	TOTAL SHEETS 37	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G70	