

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	700	700				
40600300	AGGREGATE (PRIME COAT)	TON	140	140					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	458	458				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	458	458				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	300	300					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	552	552				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2900	2900					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
42001300	PROTECTIVE COAT	SQ YD	25	25					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1400	1400				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	34500	34500													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100													
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	70	70													
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	16	16													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	900	900													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2680	2680													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	473	473													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29480	29480													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1550	1550													
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200	200													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	700	700													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	350	350													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	473	473													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29480	29480													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1550	1550													
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200	200													

* Specialty Items