

SUMMARY OF QUANTITIES				URBAN 100% STATE					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				URBAN 100% STATE					CONSTRUCTION TYPE CODE																
CODE NO	ITEM	UNIT	TOTAL QUANTITIES															CODE NO	ITEM	UNIT	TOTAL QUANTITIES																		
				1000																		1000																	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	55	55														70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10950	10950																	
40600300	AGGREGATE (PRIME COAT)	TON	249	249														*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1373	1373																	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	38	38														*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	71058	71058																	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2														*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9727	9727																	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1252	1252														*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1475	1475																	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10441	10441														*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	910	910																	
42001300	PROTECTIVE COAT	SQ YD	372	372														*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1836	1836																	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	124294	124294														*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	623	623																	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4580	4580														78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	499	499																	
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	2255	2255														88600600	DETECTOR LOOP REPLACEMENT	FOOT	3200	3200																	
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	1049	1049														X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4																	
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	983	983														X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	140	140																	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1800	1800														X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	5377	5377																	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	71	71														44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	325	325																	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4														Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	162	162																	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	67	67																																			
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	7	7																																			
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	62	62																																			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																																			
67100100	MOBILIZATION	L SUM	1	1																																			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																																			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																																			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	32848	32848																																			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1373	1373																																			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	71058	71058																																			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9727	9727																																			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1475	1475																																			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	910	910																																			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1836	1836																																			