

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	43.2	43.2													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	46	46				
40600300	AGGREGATE (PRIME COAT)	TON	39	39					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	394	394				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					X4421803	CLASS D PATCHES, TYPE II, 13 1/4 INCH	SQYD	65	65				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	243	243					X4421807	CLASS D PATCHES, TYPE III, 13 1/4 INCH	SQYD	40	40				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	841	841					X4421809	CLASS D PATCHES, TYPE IV, 13 1/4 INCH	SQYD	350	350				
42001300	PROTECTIVE COAT	SQ YD	8	8													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9723	9723													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	25	25													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	173	173													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2040	2040													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	36.4													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7472	7472													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	218	218													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	150	150													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	33	33													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	227	227													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	36.4													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7472	7472													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	218	218													
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	150	150													
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	33	33													
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	70	70													

* SPECIALTY ITEMS

FILE NAME =	USER NAME = abrauch	DESIGNED -	REVISED -
chpw_work\FWIDOT\ABREU\AH\0137686\0154309-Designdgn		DRAWN -	REVISED -
PLOT SCALE = 50:2000' / IN.		CHECKED -	REVISED -
PLOT DATE = 4/17/2009		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GARY'S MILL ROAD
SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3549	2 RS-2	DUPAGE	15	3