SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	6	6					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17					
40600300	AGGREGATE (PRIME COAT)	TON	82	82					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	275	275					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	258	258					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1711	1711					
42001300	PROTECTIVE COAT	SQ YD	560	560					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2000	2000					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20360	20360					
44000600	SIDEWALK REMOVAL	SQ FT	2000	2000					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1500	1500					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1530	1530					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	296	296					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	276	276					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	815	815					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	30	30					
55039700	STORM SEWERS TO BE CLEANED	FOOT	1200	1200					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	6	6					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30	30					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	30	30					
60404940	FRAMES AND GRATES, TYPE 23	EACH	18	18					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3040	3040					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7180	7180					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1800	1800					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200	200					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	680	680					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	370	370					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1020	1020					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7180	7180					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1800	1800					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200	200					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	680	680					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	370	370					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	150	150					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	21	21					
88600600	DETECTOR LOOP REPLACEMENT	FOOT	875	875					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	150	150					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	802	802					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\PWIDOT\MOSSSE\d0137501\D154809-sht-plan.dgn	USER NAME = mossse	DESIGNED -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	DRAWN -	REVISED -
	PLOT DATE = 4/14/2009	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HALSTED STREET (15TH ST. TO IL. RTE. 1 CUT OFF)
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2886	2009-051 RS	COOK	24	3
		CONTRACT NO. 60G92		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT