

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	136	136														
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7														
40600300	AGGREGATE (PRIME COAT)	TON	34	34														
40600895	CONSTRUCTING TEST STRIP	EACH	3	3														
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	4246	4246														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1416	1416														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	274	274														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5485	5485														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19070	19070														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	25	25														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1828	1828														
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19070	19070														
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	25	25														
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	171	171														
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4														
XX003535	AGGREGATE BASE COURSE, TYPE B, 2"	SO YD	16850	16850														
XX006047	PULVERIZATION	SO YD	16850	16850														

* SPECIALITY ITEMS