

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN 100% STATE		ROADWAY 1000						CODE NO	ITEM	UNIT	URBAN 100% STATE						
			TOTAL QUANTITIES											TOTAL QUANTITIES	ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	86		86						*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	220		220				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10		10						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	220		220				
40600300	AGGREGATE (PRIME COAT)	TON	35		35						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4		51.4				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6		6						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	730		730				
40600895	CONSTRUCTING TEST STRIP	EACH	1		1						70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	61		61						70102425	TRAFFIC CONTROL AND PROTECTION, STANDARD 701600	L SUM	1		1				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	320		320						70102435	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1452		1452															
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	16756		16756															
44002218	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 1/2"	SQ YD	1230		1230															
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	1065		1065															
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	60		60															
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	105		105															
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	480		480															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6															
67100100	MOBILIZATION	L SUM	1		1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2175		2175															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146		146															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21108		21108															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	638		638															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	270		270															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	49		49															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7723		7723															
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146		146															
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21108		21108															
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	638		638															
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	270		270															
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	49		49															

FILE NAME =
c:\pwworking\pwworking\project\36065\mcl.blvd.dgn

USER NAME = yoon/s
PLOT SCALE = 500000' / IN.
PLOT DATE = 4/18/2009

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

McLEAN BLVD. (SPRING ST. TO LANCASTER CIRCLE)
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
2509 94RS KANE 20 3
CONTRACT NO. 60H04
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT

Rev.