

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
20201006	GRADING AND SHAPING SHOULDERS	UNIT	132	132
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	113	113
40600300	AGGREGATE (PRIME COAT)	TON	60	60
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	190	190
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	237	237
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2530	2530
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	30100	30100
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1057	1057
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	84	84
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	393	393
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	280	280
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	133	133
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	530	530
55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4790	4790
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29900	29900
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	650	650
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	790	790
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	36	36
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	799	799
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29900	29900
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	650	650
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	790	790
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36	36
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	369	369
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	369	369
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	575	575
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1270	1270
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15

* SPECIALTY ITEM

FILE NAME = P:\2007\ME07080_Ver-Var-Phil\Cadd\MOIS_SheridanRd\Shts\0350Dsh-Sheridan.dgn
 USER NAME = M.Milenna
 MILLENNA PROFESSIONAL SERVICES



200 22ND Street, Suite 216, Lombard, IL 60148
 630.705.8110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - IVN	REVISED - ---
DRAWN - IVN	REVISED - ---
CHECKED - BPD	REVISED - ---
DATE - 4/16/2009	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SHERIDAN ROAD
BLODGETT AVE TO IL RTE 137 (BUCKLEY RD)

SUMMARY OF QUANTITIES

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	(113_&113_W)_RS-10_	LAKE	18	3
CONTRACT NO. 60H08			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

P:\2007\ME07080_Ver-Var-Phil\Cadd\MOIS_SheridanRd\Shts\0350Dsh-Sheridan.dgn