

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	110	110				
40600300	AGGREGATE (PRIME COAT)	TON	47	47					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7010	7010				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1040	1040				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	600				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	150	150					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	280	280				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	975	975					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	175	175				
42001300	PROTECTIVE COAT	SO YD	135	135					88600600	DETECTOR LOOP REPLACEMENT	FOOT	702	702				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	36	36					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	11580	11580					X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	105	105				
44000600	SIDEWALK REMOVAL	SO FT	36	36					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	457	457				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	7	7				
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	4	4													
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	336	336													
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	20	20													
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	27	27													
55039700	STORM SEWERS TO BE CLEANED	FOOT	550	550													
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	12	12													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2100	2100													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	110	110													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7010	7010													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1040	1040													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	600	600													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	280	280													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	700	700													