

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100% STATE					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100% STATE				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	400	400				
40600300	AGGREGATE (PRIME COAT)	TON	42	42					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	218	218				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	7	7					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8800	8800				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1570	1570				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	190	190					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1370	1370				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	685	685					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	235	235				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1790	1790					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	265	265				
42001300	PROTECTIVE COAT	SQ YD	5	5					88600600	DETECTOR LOOP REPLACEMENT	FOOT	500	500				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	60	60					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20683	20683					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	840	840				
44000600	SIDEWALK REMOVAL	SQ FT	60	60					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	23	23				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	15	15													
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	3000	3000													
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	2140	2140													
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	348	348													
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	160	160													
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3510	3510													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	218	218													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8800	8800													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1570	1570													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1370	1370													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	235	235													
										* SPECIALTY ITEMS							