

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	47	47
40600300	AGGREGATE (PRIME COAT)	TON	312	312
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	503	503
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	483	483
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6,561	6,561
42001300	PROTECTIVE COAT	SQ YD	722	722
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	400	400
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	78,111	78,111
44000600	SIDEWALK REMOVAL	SQ FT	400	400
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,000	3,000
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,875	2,875
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	50	50
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,739	1,739
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	187	187
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	524	524
55039700	STORM SEWERS TO BE CLEANED	FOOT	3,744	3,744
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	8	8
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	24	24
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	238	238
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000 URBAN
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,284	7,284
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,000	1,000
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25,000	25,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,000	5,000
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,200	1,200
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	400	400
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,200	1,200
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	801	801
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,000	1,000
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25,000	25,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,000	5,000
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,200	1,200
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	400	400
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,200	1,200
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	535	535
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4,215	4,215
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	60	60
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,281	3,281
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	117	117
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

\* SPECIALTY ITEM

FILE NAME = D:\60H17-ah-500.dgn  
PLOT DATE = 4/15/2009

**CR & A**  
CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	APRIL 14, 2009	REVISED -	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
103rd STREET

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 10+32 TO STA. 116+77

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1574	(0808 & 0809) RS-2	COOK	20	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H17	